

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
804	125R1RS	CHAMPAIGN	50	18

## SCHEDULE OF QUANTITIES

### 4" SOLID WHITE (CONT'D)

80+98.0	TO	88+13.3	30.7' RT	715.3
88+96.7	TO	95+16.7	30.7' RT	620.0
112+87.9	TO	114+05.9	31.0' RT	118.0
115+08.7	TO	116+06.7	7.0' RT	98.0
119+19.2	TO	122+80.0	31.0' RT	360.8
123+84.0	TO	125+12.0	7.0' RT	128.0
131+48.7	TO	132+84.0	31.0' RT	135.3
131+85.0	TO	132+83.0	7.0' RT	98.0
133+85.0	TO	135+00.0	31.0' LT	115.0
133+87.0	TO	134+85.0	7.0' LT	98.0
80+76.0	TO	132+10.0	30.7' LT	5134.0
134+23.4	TO	135+00.0	30.7' LT	76.6
95+89.9	TO	107+02.0	30.7' RT	1112.1
107+90.0	TO	112+87.9	30.7' RT	497.9
114+90.0	TO	123+30.0	30.7' RT	840.0
123+82.0	TO	132+48.7	30.7' RT	866.7
134+68.7	TO	135+00.0	30.7' RT	31.3

#### FLORIDA AVE.

0+58.8	TO	0+78.9	10.5' RT	20.1
--------	----	--------	----------	------

#### KIRBY AVE.

0+54.4	TO	1+13.3	7.3' LT	58.9
0+54.4	TO	1+13.3	18.3' LT	58.9

#### ST. MARY'S RD.

0+52.1	TO	1+11.2	11.0' LT	59.1
--------	----	--------	----------	------

#### FOX DR.

0+56.2	TO	0+92.8	4.0' LT	36.6
--------	----	--------	---------	------

#### DEVONSHIRE DR.

0+73.0	TO	1+20.6	11.0' LT	47.6
--------	----	--------	----------	------

#### KNOLLWOOD DR.

7+12.5	TO	7+60.0	11.5' LT	47.5
--------	----	--------	----------	------

#### WINDSOR RD. (E)

10+60.3	TO	10+97.4	42.8' LT	37.1
---------	----	---------	----------	------

#### WINDSOR RD. (W)

9+12.6	TO	9+36.8	36.0' RT	24.2
--------	----	--------	----------	------

#### BURWASH

0+60.0	TO	0+73.5	12.0' LT	13.5
--------	----	--------	----------	------

#### ARBOUR TOWNE PL.

0+90.6	TO	1+16.6	14.0' RT	26.0
0+90.6	TO	1+16.6	14.0' LT	26.0

#### CURTIS RD. (E)

15+62.0	TO	15+90.7	6.0' LT	28.7
---------	----	---------	---------	------

#### CURTS RD. (W)

13+87.0	TO	14+38.0	8.0' RT	51.0
---------	----	---------	---------	------

SUB-TOTAL = 13,944.0

### THERMOPLASTIC PAVEMENT MARKING - 4" WHITE (DOUBLE)

STA.	TO	STA.	O/S	O/S	FOOT
------	----	------	-----	-----	------

#### WINDSOR AVE. (E)

10+60.3	TO	10+97.4	12.0' LT	TO	15.5' LT	74.1
10+60.3	TO	10+97.4	18.3' LT			74.1

#### WINDSOR RD. (W)

9+12.6	TO	9+36.8	6.0' RT	&	12.0' RT	48.5
--------	----	--------	---------	---	----------	------

SUB-TOTAL = 196.7

GRAND TOTAL = 43,718.5

USE = 43,719.0

### 78000400

#### THERMOPLASTIC PAVEMENT MARKING - 6" WHITE (CROSS-WALK)

##### US 45

STA.	FOOT
26+19.0	112.5
26+25.0	112.5
27+12.0	96.0
27+17.0	96.0
70+57.0	81.0
70+63.0	81.0
80+64.0	104.0
80+70.0	104.0
132+89.0	108.5
132+95.0	108.5

##### FLORIDA AVE.

0+46.8	108.1
0+52.8	106.8

##### KIRBY AVE.

0+42.4	106.0
0+48.4	102.7

##### FOX DR.

0+44.2	78.0
0+50.2	65.8

##### DEVONSHIRE DR.

0+61.0	60.0
0+67.0	54.0

##### KNOLLWOOD DR.

6+45.7	74.3
6+51.7	85.0

##### WINDSOR RD. (W)

9+41.0	118.5
9+47.0	121.2

##### CURTIS RD. (W)

14+44.0	98.5
14+50.0	98.5

SUB-TOTAL = 2281.4

#### THERMOPLASTIC PAVEMENT MARKING - 6" WHITE (RAILROAD CROSSING)

##### CURTIS RD. (E)

STA.	TO	STA.	FOOT
15+62.0	TO	15+90.7	345.0

SUB-TOTAL = 345.0

#### THERMOPLASTIC PAVEMENT MARKING - 6" WHITE (MEDIAN)

##### ARBOUR TOWNE PL.

STA.	TO	STA.	O/S	FOOT
0+33.1	TO	0+88.8	LT	153.3
0+29.4	TO	0+80.5	RT	172.6

SUB-TOTAL = 325.9

GRAND TOTAL = 2,952.3

USE = 2593.0

### 78000600

#### THERMOPLASTIC PAVEMENT MARKING - 12" WHITE (DIAGONAL)

##### ARBOUR TOWNE PL.

STA.	TO	STA.	O/S	FOOT
0+33.1	TO	0+88.8	LT	67.1
0+29.4	TO	0+80.5	RT	62.2

##### WINDSOR AVE. (E)

10+60.3	TO	10+97.4	LT	12.0
---------	----	---------	----	------

##### WINDSOR RD. (W)

9+12.6	TO	9+36.8	RT	8.0
--------	----	--------	----	-----

SUB-TOTAL = 149.3

#### THERMOPLASTIC PAVEMENT MARKING - 12" WHITE (DIAGONAL)

##### WINDSOR RD. (W)

STA.	TO	STA.	O/S	FOOT
9+12.6	TO	9+36.8	LT	8.0

SUB-TOTAL = 8.0

GRAND TOTAL = 157.3

USE = 158.0

### 78000650

#### THERMOPLASTIC PAVEMENT MARKING - 24" WHITE (STOP-BAR)

##### US 45

STA.	FOOT
26+15.0	57.0
27+21.0	53.0
39+32.0	33.0
40+62.0	48.0
56+81.0	36.0
58+07.0	36.0
69+64.0	44.0
70+69.0	38.0
79+34.0	59.0
80+74.0	51.0
122+78.0	38.0
123+82.0	38.0
132+85.0	56.0
133+85.0	55.0

##### KIRBY AVE.

0+53.0	51.0
--------	------

##### FLORIDA AVE.

0+58.8	55.0
--------	------

##### ST. MARY'S RD.

0+52.1	38.0
--------	------

##### FOX DR.

0+56.2	38.0
--------	------

##### DEVONSHIRE DR.

0+73.0	28.0
--------	------

##### KNOLLWOOD DR.

7+60.0	38.0
--------	------

##### WINDSOR RD. (E)

10+50.0	68.5
---------	------

##### WINDSOR RD. (W)

9+36.5	64.0
--------	------

##### BURWASH AVE.

0+60.0	20.0
--------	------

##### ARBOUR TOWNE PL.

0+51.0	12.0
0+59.8	18.0

##### CURTIS RD. (W)

14+38.0	38.0
---------	------

GRAND-TOTAL = 1,110.5

USE = 1,110.0

### 78100100

#### RAISED REFLECTIVE PAVEMENT MARKERS

##### TWO-WAY ONE-WAY

STA.	TO	STA.	AMBER	CRYSTAL
40+62.0	TO	42+89.0	12.0	16.0
42+89.0	TO	54+81.0	60.0	30.0
54+81.0	TO	60+07.0	22.0	17.0
60+07.0	TO	75+64.0	78.0	39.0
75+64.0	TO	84+10.0	38.0	41.0
84+10.0	TO	88+05.0	20.0	10.0
89+05.0	TO	95+09.0	30.0	18.0
96+09.0	TO	106+98.0	55.0	30.0
107+98.0	TO	114+10.0	30.0	18.0
115+07.0	TO	122+80.0	38.0	32.0
123+82.0	TO	131+85.0	40.0	25.0
131+85.0	TO	135+00.0	8.0	28.0

SUB-TOTALS = 431.0

GRAND-TOTAL = 735.0

### 88600100

#### DETECTOR LOOPS, TYPE 1

##### INTERSECTION FOOT

KIRBY AVE./FLORIDA AVE.	2087.0
ST. MARY'S/FOX DR.	1147.0
DEVONSHIRE DR.	820.0
WINDSOR RD.	1721.0
CURTIS RD.	1393.0
KNOLLWOOD DR.	847.0
ARBOURTOWNE PL.	865.0
BURWASH AVE.	639.0

TOTAL = 9519.0

### X4033000

#### SEAL COAT AGGREGATE FM-01 (SPECIAL)

STA.	TO	STA.	LENGTH	SQ YD	TON
85+00.0	TO	99+28.1	1,428.1	317.4	3.2
99+28.1	TO	135+00.0	3,571.9	793.8	7.9
85+00.0	TO	99+28.1	1,428.1	317.4	3.2
99+28.1	TO	135+00.0	3,571.9	793.8	7.9

TOTAL = 22.2

USE = 23.0

### X4032500

#### BITUMINOUS MATERIALS (COVER & SEAL COAT), SPECIAL

STA.	TO	STA.	LENGTH	SQ YD	GAL
85+00.0	TO	99+28.1	1,428.1	317.4	95.2
99+28.1	TO	135+00.0	3,571.9	793.8	238.1
85+00.0	TO	99+28.1	1,428.1	317.4	95.2
99+28.1	TO	135+00.0	3,571.9	793.8	238.1

TOTAL = 666.7

USE = 667

### Z0070100

#### SURVEY MONUMENT COVER ASSEMBLY

STA.	EACH
61+41.92	1.0
75+10.71	1.0
79+24.53	1.0
85+77.64	1.0

TOTAL = 4.0