

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	110-4,5MRS	VERMILION	13	5

SCHEDULE OF QUANTITIES

THERMOPLASTIC PAVEMENT MARKING - LINE 4"

EB EXIT RAMP "A"

STATION	TO	STATION	OFFSETS	COLOR	TYPE	FEET
107+39.08		107+60.23	15' LT, 14' LT	YELLOW	SOLID	21.2
107+60.23		108+00.00	14' LT, 14.5' LT	YELLOW	SOLID	39.8
108+00.00		108+24.16	14.5' LT, 15' LT	YELLOW	SOLID	24.2
107+39.08		107+60.23	1' LT, 0' LT	WHITE	SOLID	21.2
107+60.23		108+25.16	0' LT	WHITE	SOLID	64.9
108+25.16		108+47.25	0' RT, 3' RT	WHITE	SOLID	22.1
TOTAL =						194.0

WB EXIT RAMP "D"

STATION	TO	STATION	OFFSETS	COLOR	TYPE	FEET
105+63.00		105+83.50	3' LT, 0' LT	WHITE	SOLID	20.5
105+83.50		109+05.31	0' LT	WHITE	SOLID	321.8
105+78.50		105+90.30	15.5' RT, 14' RT	YELLOW	SOLID	12.0
105+90.30		109+05.31	14' RT	YELLOW	SOLID	315.0
TOTAL =						670.0

THERMOPLASTIC PAVEMENT MARKING - LINE 6"

EB EXIT RAMP "A"

STATION	TO	STATION	OFFSETS	COLOR	TYPE	FEET
108+62.00		108+91.50	11' LT, 46' LT	WHITE	SOLID	47.0
108+62.00		109+12.00	11' LT, 29' RT	WHITE	SOLID	64.5
108+91.50		109+12.00	46' LT, 29' RT	WHITE	SOLID	78.0
TOTAL =						190.0

WB EXIT RAMP "D"

STATION	TO	STATION	OFFSETS	COLOR	TYPE	FEET
104+99.25		105+17.50	23' LT, 46' RT	WHITE	SOLID	71.0
104+99.25		105+46.00	23' LT, 11' RT	WHITE	SOLID	58.0
105+17.50		105+46.00	46' RT, 11' RT	WHITE	SOLID	45.5
TOTAL =						175.0

THERMOPLASTIC PAVEMENT MARKING - LINE 12"

EB EXIT RAMP "A"

STATION	TO	STATION	OFFSETS	COLOR	TYPE	FEET
108+70.00		108+85.00	7.5' LT, 33' LT	WHITE	SOLID	29.0
108+76.50		108+87.50	4' LT, 23' LT	WHITE	SOLID	22.0
108+82.50		108+85.00	0.5' LT, 5' LT	WHITE	SOLID	5.0
108+88.00		108+92.00	4' RT, 4' LT	WHITE	SOLID	9.0
108+94.00		108+95.00	8' RT, 6' RT	WHITE	SOLID	3.0
108+88.00		108+94.50	39' LT, 35.5' LT	WHITE	SOLID	8.0
108+85.00		108+97.00	33' LT, 26' LT	WHITE	SOLID	15.0
108+88.00		109+00.00	23' LT, 16.5' LT	WHITE	SOLID	15.0
108+90.00		109+02.50	13' LT, 6.5' LT	WHITE	SOLID	15.0
108+93.00		109+05.00	3.5' LT, 3' RT	WHITE	SOLID	15.0
108+95.00		109+07.50	6' RT, 13' RT	WHITE	SOLID	15.0
109+05.50		109+10.00	20' RT, 22.5' RT	WHITE	SOLID	5.0
TOTAL =						156.0

WB EXIT RAMP "D"

STATION	TO	STATION	OFFSETS	COLOR	TYPE	FEET
105+02.00		105+13.00	12' LT, 6' LT	WHITE	SOLID	12.0
105+05.00		105+15.50	2.5' LT, 3.5' RT	WHITE	SOLID	12.0
105+07.00		105+18.00	7.5' RT, 13.5' RT	WHITE	SOLID	13.0
105+10.00		105+21.00	17' RT, 23' RT	WHITE	SOLID	13.0
105+12.50		105+23.50	27' RT, 33' RT	WHITE	SOLID	13.0
105+13.00		105+14.00	6' LT, 8' LT	WHITE	SOLID	3.0
105+15.50		105+19.50	3.5' RT, 4' LT	WHITE	SOLID	9.0
105+22.00		105+24.50	5' RT, 0' RT	WHITE	SOLID	6.0
105+21.00		105+24.50	23' RT, 15' RT	WHITE	SOLID	9.0
105+27.50		105+30.00	8.5' RT, 3' RT	WHITE	SOLID	6.0
105+23.50		105+35.50	33.5' RT, 6' RT	WHITE	SOLID	30.0
105+38.00		105+41.50	17' RT, 9' RT	WHITE	SOLID	9.0
TOTAL =						135.0

THERMOPLASTIC PAVEMENT MARKING - LINE 24"

EB EXIT RAMP "A"

STATION	TO	STATION	OFFSETS	COLOR	TYPE	FEET
108+63.00		108+76.00	35' LT, 23' LT	WHITE	SOLID	18.0
108+71.50		108+81.00	14' RT, 1' LT	WHITE	SOLID	18.0
TOTAL =						36.0

WB EXIT RAMP "D"

STATION	TO	STATION	OFFSETS	COLOR	TYPE	FEET
105+28.00		105+36.50	2' RT, 14' LT	WHITE	SOLID	18.0
105+34.00		105+46.50	21' RT, 34' RT	WHITE	SOLID	18.0
TOTAL =						36.0

TEMPORARY RAMP

EB EXIT RAMP "A"

STATION	OFFSETS	SQ YDS
107+39.08	0' LT	15.1
108+74.91	54' LT	17.0
108+96.14	38.5' RT	17.0
109+04.08	EOP	43.3
TOTAL =		93.0

WB EXIT RAMP "D"

STATION	OFFSETS	SQ YDS
105+05.31	EOP	39.4
105+13.03	35' LT	17.0
105+33.85	53' RT	17.0
109+05.31	0' LT	15.1
TOTAL =		89.0