

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72		PIATT	13	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

• D5 ANNUAL PATCHING 2007-1

LOCATION OF WORK:  
 I-72  
 PIATT  
 COUNTY  
 STA. 932+59.23  
 TO  
 STA. 1421+61.77  
 RURAL  
 100% STATE

CONSTRUCTION TYPE CODE:  
 J000  
 TOTAL  
 QUANTITY

CODE NO	ITEM	UNIT	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	72.0
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	216.0
44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SQ YD	1,065.0
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SQ YD	11.0
44002229	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 7 1/4"	SQ YD	47.0
44200517	CLASS A PATCHES, TYPE II, 7 INCH	SQ YD	22.0
44200521	CLASS A PATCHES, TYPE III, 7 INCH	SQ YD	20.0
44200525	CLASS A PATCHES, TYPE I, 8 INCH	SQ YD	80.0
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	456.0
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	167.0
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	207.0
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	32.0
44213000	PATCHING REINFORCEMENT	SQ YD	950.0
44213200	SAW CUTS	FOOT	5,402.0
67100100	MOBILIZATION	L SUM	1.0
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3.0
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.0
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	9.5
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0
Z0017100	DOWEL BARS	EACH	80.0
Z0075300	TIE BARS	EACH	226.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_

DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

PLOT DATE = 10/10/2006  
 FILE NAME = s:\projects\70565\summary.dgn  
 USER NAME = s:\projects\70565\summary.dgn