

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	:	PIAII	13	8
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES CLASS A PATCHES

• D5 ANNUAL PATCHING 2007-1

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)	HMA REM OVER PATCH 3.25 440022XX (sq. yd)	HMA REPLACEMENT OVER PATCHES 40601005 (Tons)
					TYPE I 8" (sq. yd)	TYPE II 8" (sq. yd)	TYPE III 8" (sq. yd)	TYPE IV 8" (sq. yd)					
953+83	EASTBOUND	DL	25	6	0.0	0.0	16.7	0.0	74.0	13	16.7	18.0	3.3
956+48	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
956+71	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
956+95	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
957+70	EASTBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
958+20	EASTBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
958+55	EASTBOUND	DL	90	6	0.0	0.0	0.0	60.0	204.0	45	60.0	61.3	11.2
959+60	EASTBOUND	DL	15	6	0.0	10.0	0.0	0.0	54.0	0	10.0	11.3	2.1
960+00	EASTBOUND	DL	15	6	0.0	10.0	0.0	0.0	54.0	0	10.0	11.3	2.1
960+40	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
961+31	EASTBOUND	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
963+10	EASTBOUND	DL	20	6	0.0	13.3	0.0	0.0	64.0	10	13.3	14.7	2.7
964+05	EASTBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
SHEET TOTALS					16.0 (sq. yd)	58.7 (sq. yd)	16.7 (sq. yd)	60.0 (sq. yd)	766.0 (ft)	68.0 (Each)	151.3 (sq. yd)	168.7 (sq. yd)	30.7 (Tons)

CLASS A PATCHES

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)	HMA REM OVER PATCH 5 440022XX (sq. yd)	HMA REPLACEMENT OVER PATCHES 40601005 (Tons)
					TYPE I 8" (sq. yd)	TYPE II 8" (sq. yd)	TYPE III 8" (sq. yd)	TYPE IV 8" (sq. yd)					
1035+93.94	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	3.0
SHEET TOTALS					0.0 (sq. yd)	8.0 (sq. yd)	0.0 (sq. yd)	0.0 (sq. yd)	60.0 (ft)	0.0 (Each)	8.0 (sq. yd)	10.7 (sq. yd)	3.0 (Tons)

PLOT DATE = 10/24/2006
 FILE NAME = c:\projects\0508006 (v.8)\70565 text.dgn
 PLOT SCALE = 42.3525' / IN.
 USER NAME = stults,j

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT.
HORIZ.
DATE

DRAWN BY
CHECKED BY