

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	1	PIAII	13	10
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

CLASS A PATCHES

• D5 ANNUAL PATCHING 2007-1

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)	HMA REM OVER PATCH 3.25 440022XX (sq. yd)	HMA REPLACEMENT OVER PATCHES 40601005 (Tons)
					TYPE I 8" (sq. yd)	TYPE II 8" (sq. yd)	TYPE III 8" (sq. yd)	TYPE IV 8" (sq. yd)					
1297+85	EASTBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
1300+00	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1300+05	EASTBOUND	DL	15	6	0.0	10.0	0.0	0.0	54.0	0	10.0	11.3	2.1
1300+20	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1300+40	EASTBOUND	DL	10	12	0.0	13.3	0.0	0.0	68.0	0	13.3	16.0	2.9
1300+55	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1300+70	EASTBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
1300+75	EASTBOUND	DL	8	12	0.0	10.7	0.0	0.0	64.0	0	10.7	13.3	2.4
1300+96	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1301+45	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1301+80	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1303+00	EASTBOUND	DL	10	12	0.0	13.3	0.0	0.0	68.0	0	13.3	16.0	2.9
1306+95	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1309+90	EASTBOUND	DL	10	12	0.0	13.3	0.0	0.0	68.0	0	13.3	16.0	2.9
1321+56	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1321+87	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1322+15	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1348+50	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1349+55	EASTBOUND	DL	12	12	0.0	0.0	16.0	0.0	72.0	0	16.0	18.7	3.4
1349+95	EASTBOUND	DL	10	12	0.0	13.3	0.0	0.0	68.0	0	13.3	16.0	2.9
1374+47	EASTBOUND	DL	30	6	0.0	0.0	20.0	0.0	84.0	15	20.0	21.3	3.9
1375+40	EASTBOUND	DL	30	6	0.0	0.0	20.0	0.0	84.0	15	20.0	21.3	3.9
1379+30	EASTBOUND	DL	100	6	0.0	0.0	0.0	66.7	224.0	50	66.7	68.0	12.4
1379+30	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1379+30	EASTBOUND	DL	20	12	0.0	0.0	0.0	26.7	88.0	10	26.7	29.3	5.3
1384+80	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1385+00	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1386+10	EASTBOUND	DL	15	6	0.0	10.0	0.0	0.0	54.0	0	10.0	11.3	2.1
1387+40	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1391+58	EASTBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
1395+40	EASTBOUND	DL	15	12	0.0	0.0	20.0	0.0	78.0	0	20.0	22.7	4.1
1400+10	EASTBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1458+80	EASTBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1480+00	EASTBOUND	RAMP	16	6	0.0	10.7	0.0	0.0	56.0	0	10.7	12.0	2.2
1386+22	WESTBOUND	DL	8	12	0.0	10.7	0.0	0.0	64.0	0	10.7	13.3	2.4
SHEET TOTALS					24.0 (sq. yd)	213.3 (sq. yd)	76.0 (sq. yd)	93.3 (sq. yd)	2202.0 (ft)	90.0 (Each)	406.7 (sq. yd)	480.0 (sq. yd)	87.4 (Tons)

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DRAWN BY _____
CHECKED BY _____