

SCHEDULE OF QUANTITIES

CLASS A PATCHES

LOCATION #1 - I-57

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
:	::	***	18	12
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

- 57 & 74
- D5 ANNUAL PATCHING 2007-3
- CHAMPAIGN, DOUGLAS, & VERMILION

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)	HMA REM OVER PATCH 3.25 44002213 (sq. yd)	HMA REPLACEMENT OVER PATCHES 40601005 (Tons)
					TYPE I 8" (sq. yd)	TYPE II 8" (sq. yd)	TYPE III 8" (sq. yd)	TYPE IV 8" (sq. yd)					
547+69.73	NORTHBOUND	PL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
547+69.73	NORTHBOUND	DL	8	12	0.0	10.7	0.0	0.0	64.0	0	10.7	13.3	2.4
558+99.65	NORTHBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
559+47.17	NORTHBOUND	DL	18	6	0.0	12.0	0.0	0.0	60.0	0	12.0	13.3	2.4
562+63.97	NORTHBOUND	DL	40	6	0.0	0.0	0.0	26.7	104.0	20	26.7	28.0	5.1
563+11.49	NORTHBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
581+38.37	NORTHBOUND	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
581+85.89	NORTHBOUND	DL	12	6	0.0	8.0	0.0	0.0	48.0	0	8.0	9.3	1.7
582+01.73	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
582+22.85	NORTHBOUND	DL	14	6	0.0	9.3	0.0	0.0	52.0	0	9.3	10.7	1.9
584+34.05	NORTHBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
656+51.81	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
660+47.81	NORTHBOUND	DL	14	6	0.0	9.3	0.0	0.0	52.0	0	9.3	10.7	1.9
661+74.53	NORTHBOUND	PL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
670+03.49	NORTHBOUND	PL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
686+77.25	NORTHBOUND	PL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
686+93.09	NORTHBOUND	DL	14	6	0.0	9.3	0.0	0.0	52.0	0	9.3	10.7	1.9
688+14.53	NORTHBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
688+25.09	NORTHBOUND	DL	8	12	0.0	10.7	0.0	0.0	64.0	0	10.7	13.3	2.4
739+83.65	NORTHBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
745+38.05	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
745+53.89	NORTHBOUND	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
747+01.73	NORTHBOUND	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
756+52.13	NORTHBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
832+18.37	NORTHBOUND	DL,LWL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
SHEET TOTALS					24.0 (sq. yd)	140.0 (sq. yd)	0.0 (sq. yd)	26.7 (sq. yd)	1224.0 (ft)	20.0 (Each)	190.7 (sq. yd)	230.7 (sq. yd)	42.0 (Tons)

PLOT DATE = 10/25/2006
 FILE NAME = c:\projects\4588206 (v.8)\70567 text.dgn
 PLOT SCALE = 42,352" / IN.
 USER NAME = stults,jr

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____

DRAWN BY _____
 CHECKED BY _____