

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
:	::	:::	18	14
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

SCHEDULE OF QUANTITIES

CLASS A PATCHES

LOCATION #2 - I-57

- 57 & 74
- D5 ANNUAL PATCHING 2007-3
- CHAMPAIGN, DOUGLAS, & VERMILION

STATION	DIRECTION	LANE	LENGTH (ft)	WIDTH (ft)	PATCH AREA				SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (Each)	PATCHING REINFORCEMENT 44213000 (sq. yd)	HMA REM OVER PATCH 3.25 44002213 (sq. yd)	HMA REPLACEMENT OVER PATCHES 40601005 (Tons)
					TYPE I 7" (sq. yd)	TYPE II 7" (sq. yd)	TYPE III 7" (sq. yd)	TYPE IV 7" (sq. yd)					
1019+40.40	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1021+51.60	NORTHBOUND	DL	8	6	0.0	5.3	0.0	0.0	40.0	0	5.3	6.7	1.2
1022+04.40	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1022+57.20	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1026+79.60	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1031+54.80	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1032+07.60	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1036+82.80	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1038+94.00	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1050+55.60	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1055+83.60	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1056+33.60	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1063+22.80	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1063+75.60	NORTHBOUND	DL	10	6	0.0	6.7	0.0	0.0	44.0	0	6.7	8.0	1.5
1068+50.80	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1074+84.40	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1075+37.20	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1076+95.60	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1078+01.20	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1083+29.20	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1085+40.40	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1112+33.20	NORTHBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
1118+66.80	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1119+72.40	NORTHBOUND	DL	6	6	4.0	0.0	0.0	0.0	36.0	0	4.0	5.3	1.0
1122+89.20	NORTHBOUND	DL	6	12	0.0	8.0	0.0	0.0	60.0	0	8.0	10.7	1.9
SHEET TOTALS					84.0 (sq. yd)	28.0 (sq. yd)	0.0 (sq. yd)	0.0 (sq. yd)	960.0 (ft)	0.0 (Each)	112.0 (sq. yd)	148.0 (sq. yd)	26.9 (Tons)

PLOT DATE = 10/25/2006
 FILE NAME = c:\projects\4588206 (v.8)\70567 text.dgn
 PLOT SCALE = 42,352" / IN.
 USER NAME = stults,jr

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____

DRAWN BY _____
 CHECKED BY _____