CONTRACT NO. 72792

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	24	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* FAS 728 & FAU 8136
** D 6 RESURFACING 2007-1

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

80% FED/20% STATE

RS — M

LOCATION OF WORK				LOCATION A IL 138 FROM GREEN ST IN WHITE CITY TO OLD 66	LOCATION B IL 138 FROM OLD 66 TO ILLINOIS ST	LOCATION C STAUNTON RD E OF I-55 TO 0.5 MILES E OF I-55
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	I000	I000	I000
35800100	PREPARATION OF BASE	SQ YD	169	31		138
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	12	2		10
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19.2	7.0	6.2	6.0
40600300	AGGREGATE (PRIME COAT)	TON	102	37	33	32
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1,198	605		593
40600895	CONSTRUCTING TEST STRIP	EACH	2	1		1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,050	548		502
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	685	212		473
40600990	TEMPORARY RAMP	SQ YD	529	353	78	98
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1,737	1,019.5	717.5	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	889			889
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	201	26	130	45
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	18,596.	2,294	16,302	
44200094	PAVEMENT PATCHING, TYPE II, 8 INCH	SQ YD	720	300		420
44200099	PAVEMENT PATCHING, TYPE III, 8 INCH	SQ YD	145	75		70
44200101	PAVEMENT PATCHING, TYPE IV, 8 INCH	SQ YD	115	70		45
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SQ YD	80		80	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	495	251		244
48203100	HOT-MIX ASPHALT SHOULDERS	TON	2,118	866	521	731
67100100	MOBILIZATION	L SUM	1	0.4	0.2	0.4

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAS 728 (IL 138) & FAU 8136 (STAUNTON ROAD)
SECTION D 6 RESURFACING 2007-1
MACOUPIN COUNTY

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY

PLOT DATE = 10/24/2006
FILE NAME = u:\Projects\d652403\sht500.dgn
PLOT SCALE = 100.000 ' / IN.
USER NAME = laughlm1