

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	24	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- FAS 728 & FAU 8136
- D 6 RESURFACING 2007-1

PAVING SCHEDULE

LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	HMA SHLD WIDTH		PAVT AREA (SQ YD)	SHLD AREA (SQ YD)	HMA SURF REM 1 1/2" (SQ YD)	BIT PRIME CT (TON)	AGG PRIME CT (TON)	LEVEL BINDER (TON)	SURF CSE N50, MIX C (TON)	SURF CSE N50, MIX D (TON)	HMA SHOULDER (TON)	INCIDENTAL HMA SURF (TON)	
			LT (FOOT)	RT (FOOT)											
LOCATION B - IL 138 EAST															
IL 138 - MAINLINE															
STA 124+82.17 TO STA 125+08.67 BK	26.50	22	8	8	64.78	47.11	111.89	0.04	0.22		5.44		3.96		
STA 39+01.32 AH TO STA 4+33.84	3,467.48	22	8	8	8,476.06	6,164.41	14,640.47	5.56	29.28		711.99		517.81		
LT PRANGE ST	24.00	VAR			91.62		91.62	0.03	0.18					7.70	
RT PRANGE ST	29.50	VAR			159.79		159.79	0.06	0.32					13.42	
LT ILLINOIS ST	163.00	VAR			699.85		699.85	0.27	1.40					58.79	
RT ILLINOIS ST	113.00	VAR			597.80		597.80	0.23	1.20					50.22	
LOCATION C - STAUNTON ROAD															
STAUNTON ROAD															
STA 51+26.00 TO STA 51+35.00	9.00	29	10	10	29.00	20.00		0.02	0.10	1.62		2.44	2.80		
STA 51+35.00 TO STA 54+35.00	300.00	29 TO 41	10	10	1,166.67	666.67		0.70	3.67	65.33		98.00	93.33		
STA 54+35.00 TO STA 57+19.00	284.00	41	10	10	1,293.78	631.11		0.73	3.85	72.45	108.68	88.36			
STA 57+19.00 TO STA 57+36.00	17.00	41 TO 43	10	10	79.33	37.78		0.04	0.23	4.44		6.66	5.29		
STA 57+36.00 TO STA 57+77.00	41.00	46	10	10	209.56	91.11		0.11	0.60	11.74		17.60	12.76		
STA 57+77.00 TO STA 58+02.00	25.00	46			127.78			0.05	0.26	7.16		10.73			
STA 58+02.00 TO STA 58+53.50	51.50	40 TO 29			197.42			0.08	0.39	11.06		16.58			
STA 58+53.50 TO STA 58+54.00	0.50	29	10		1.61	0.56		0.00	0.00	0.09		0.14	0.08		
STA 58+54.00 TO STA 65+19.00	665.00	29	10	10	2,142.78	1,477.78		1.38	7.24	120.00	179.99	206.89			
STA 65+19.00 TO STA 65+32.00	13.00	29		10	41.89	14.44		0.02	0.11	2.35		3.52	2.02		
STA 65+32.00 TO STA 65+39.24	7.24	29			23.33			0.01	0.05	1.31		1.96			
STA 65+39.24 TO STA 65+66.86	27.62	29 TO 43			110.48			0.04	0.22	6.19		9.28			
STA 65+66.86 TO STA 66+31.62	64.76	46			331.00			0.13	0.66	18.54		27.80			
STA 66+31.62 TO STA 66+59.24	27.62	43 TO 29			110.48			0.04	0.22	6.19		9.28			
STA 66+59.24 TO STA 66+71.00	11.76	29			37.89			0.01	0.08	2.12		3.18			
STA 66+71.00 TO STA 67+14.71	43.71	29		10	140.84	48.57		0.07	0.38	7.89		11.83	6.80		
STA 67+14.71 TO STA 69+55.51	240.80	29 TO 32	10	10	816.04	535.11		0.51	2.70	45.70		68.55	74.92		
STA 69+55.51 TO STA 71+90.37	234.86	30	10	10	782.87	521.91		0.50	2.61	43.84		65.76	73.07		
STA 71+90.37 TO STA 75+98.18	407.81	31 TO 24	10	10	1,246.09	906.24		0.82	4.30	69.78		104.67	126.87		
STA 75+98.18 TO STA 76+00.00	1.82	24	10	10	4.85	4.04		0.00	0.02	0.27		0.41	0.57		
STA 76+00.00 TO STA 76+96.00	96.00	24 TO 21	10	10	240.00	213.33		0.17	0.91	13.44		20.16	29.87		
RAMP C	20.00	VAR			160.66	29.65		0.07	0.38	9.00		13.50	4.15		
RAMP D	24.00	VAR			207.72	20.82		0.09	0.46	11.63		17.45	2.91		
FRONTAGE RD NORTH	130.50	VAR			813.33			0.31	1.63	45.55		68.32			
FRONTAGE RD SOUTH	60.00	VAR			273.82			0.10	0.55	15.33		23.00			
LT STA 67+50 (CE)	10.00	VAR			71.22			0.03	0.14					31.91	
RT STA 72+40 (PE)	8.00	VAR			31.14			0.01	0.06					6.10	
LT STA 74+20 (PE)	8.00	VAR			35.56			0.01	0.07					6.97	
SUBTOTALS								16,301.42	12.24	64.49	593.02	717.43	889.49	1,252.46	175.11
SUBTOTALS (PREVIOUS PAGE)								2,294.23	6.98	37.02	605.03	1,019.59	0.00	865.76	25.95
TOTALS								18,595.65	19.22	101.51	1,198.05	1,737.02	889.49	2,118.22	201.06

PLOT DATE = 10/24/2006
 FILE NAME = c:\p\projects\652483\shedsched.dgn
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FAS 728 (IL 138) & FAU 8136 (STAUNTON ROAD)
 SECTION D 6 RESURFACING 2007-1
 MACOUPIN COUNTY
 SCALE: VERT. _____
 HORIZ. _____
 DATE _____ DRAWN BY _____
 CHECKED BY _____