

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	24	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- FAS 728 & FAU 8136
- D 6 RESURFACING 2007-1

THERMOPLASTIC PAVEMENT MARKING - LINE 5"

LOCATION	LENGTH (FOOT)	# OF LINES	COLOR	QTY (FOOT)
LOCATION A - IL 138 WEST				
IL 138 - MAINLINE				
LT STA 83+68 TO STA 87+62	394	1	WHITE	394
RT STA 83+68 TO STA 92+86	918	1	WHITE	918
LT STA 88+44 TO STA 92+48	404	1	WHITE	404
LT STA 93+83 TO STA 98+63	480	1	WHITE	480
RT STA 94+23 TO STA 98+63	440	1	WHITE	440
LT STA 101+37 TO STA 106+07	470	1	WHITE	470
RT STA 101+37 TO STA 106+16	479	1	WHITE	479
LT STA 107+13 TO STA 112+63	550	1	WHITE	550
RT STA 107+48 TO STA 112+63	515	1	WHITE	515
STA 83+68 TO STA 87+53	385	2	YELLOW	777
STA 88+13 TO STA 93+68	555	2	YELLOW	1,126
STA 94+38 TO STA 98+63	425	2	YELLOW	854
STA 101+37 TO STA 105+62	425	2	YELLOW	855
STA 106+33 TO STA 112+63	630	2	YELLOW	1,269
RAMP A	238	1	WHITE	238
RAMP A	177	1	YELLOW	177
RAMP B	189	1	WHITE	189
RAMP B	171	1	YELLOW	171
RAMP C	236	1	WHITE	236
RAMP C	168	1	YELLOW	168
RAMP D	167	1	WHITE	167
RAMP D	123	1	YELLOW	123
LOCATION C - STAUNTON ROAD				
STAUNTON ROAD				
STA 51+26 TO STA 57+77	651	2	WHITE	1,302
LT STA 59+15 TO STA 64+57	542	1	WHITE	542
RT STA 59+29 TO STA 65+27	598	1	WHITE	598
RT STA 66+71 TO STA 76+96	1,025	1	WHITE	1,025
LT STA 67+15 TO STA 76+96	981	1	WHITE	981
STA 51+26 TO STA 57+39	613	2	YELLOW	1,229
STA 57+98 TO STA 65+70	772	2	YELLOW	1,555
STA 66+29 TO STA 72+72	643	2	YELLOW	1,292
STA 72+72 TO STA 76+96	424	2	YELLOW	848
RAMP C	92	1	WHITE	92
RAMP C	31	1	YELLOW	31
RAMP D	83	1	WHITE	83
RAMP D	27	1	YELLOW	27
EAST FRONTAGE RD N		2	WHITE	416
EAST FRONTAGE RD S		2	WHITE	201
TOTAL				21,222

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"

LOCATION	QTY (FOOT)
LOCATION A - IL 138 WEST	
RAMP A	40.0
RAMP C	36.0
LOCATION C - STAUNTON ROAD	
RAMP C	36.0
TOTAL	112.0

THERMOPLASTIC PAVEMENT MARKING - LINE 6"

LOCATION	LENGTH (FOOT)	# OF LINES	QTY (FOOT)
LOCATION A - IL 138 WEST			
IL 138 - MAINLINE			
STA 94+66.00 TO STA 96+36.00	170	1	170
STA 103+26.00 TO STA 105+26.00	200	1	200
STA 112+29.00 TO STA 112+63.00	34	1	34
LOCATION C - STAUNTON ROAD			
STAUNTON ROAD			
STA 54+35.00 TO STA 57+10.00	275	1	275
TOTAL			679

THERMOPLASTIC PAVEMENT MARKING - LINE 8"

LOCATION	QTY (FOOT)
LOCATION A - IL 138 WEST	
RAMP A	140.0
RAMP C	150.0
LOCATION C - STAUNTON ROAD	
RAMP C	127.0
TOTAL	417.0

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS

LOCATION	QTY (SQ FT)
LOCATION A - IL 138 WEST	
IL 138 - MAINLINE	
STA 94+80.00 LT TURN ARROW	15.6
STA 95+55.00 LT TURN ARROW	15.6
STA 96+30.00 LT TURN ARROW	15.6
STA 103+30.00 LT TURN ARROW	15.6
STA 104+20.00 LT TURN ARROW	15.6
STA 105+10.00 LT TURN ARROW	15.6
STA 112+29.00 LT TURN ARROW	15.6
LOCATION C - STAUNTON ROAD	
STAUNTON ROAD	
STA 54+35.00 LT TURN ARROW	15.6
STA 55+60.00 LT TURN ARROW	15.6
STA 56+85.00 LT TURN ARROW	15.6
TOTAL	156.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAS 728 (IL 138) & FAU 8136 (STAUNTON ROAD)  
 SECTION D 6 RESURFACING 2007-1  
 MACOUPIN COUNTY

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_

PLOT DATE = 10/24/2006  
 FILE NAME = c:\p\projects\652483\shsched.dgn  
 PLOT SCALE = 1/8"=1'-0"  
 USER NAME = laughlin-1