

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	MACOUPIN	24	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

- FAS 728 & FAU 8136
- D 6 RESURFACING 2007-1

PAINT PAVEMENT MARKING - LINE 5"

LOCATION	LENGTH (FOOT)	# OF LINES	LENGTH (FOOT)
LOCATION B - IL 138 EAST			
IL 138 - MAINLINE			
STA 124+82.17 TO STA 125+08.67 BK	26.50	2.25	59.63
STA 39+01.32 AH TO STA 4+33.84	3,467.48	2.25	7,801.83
TOTAL			7,861.46

PAINT PAVEMENT MARKING - LINE 24"

LOCATION	QTY (FOOT)
LOCATION B - IL 138 EAST	
IL 138 - MAINLINE	
STA 6+22	26
STA 5+57	23
ILLINOIS ST	
NORTH SIDE	22
SOUTH SIDE	18
TOTAL	89

RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	LENGTH (FOOT)	SPACING	QUANTITY (EACH)
LOCATION B - IL 138 EAST			
IL 138 - MAINLINE			
STA 124+82.17 TO STA 125+08.67 BK	26.50	80	1
STA 39+01.32 AH TO STA 4+33.84	3,467.48	80	44
TOTAL			45

SHORT-TERM PAVEMENT MARKING

LOCATION	LENGTH (FOOT)	# OF LINES	# OF APPLICATIONS	QTY (FOOT)
LOCATION A - IL 138 WEST				
IL 138 - MAINLINE				
STA 83+68 TO STA 98+63	1,495.00	2	2	598.00
STA 101+37 TO STA 112+63	1,126.00	2	2	450.40
LOCATION B - IL 138 EAST				
IL 138 - MAINLINE				
STA 124+82.17 TO STA 125+08.67 BK	26.50	1	2	5.30
STA 39+01.32 AH TO STA 4+33.84	3,467.48	1	2	693.50
LOCATION C - STAUNTON ROAD				
STAUNTON ROAD				
STA 70+42.00 TO STA 76+96.00	654.00	2	2	261.60
TOTAL				2,008.80

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	LENGTH (FOOT)	# OF LINES	AREA (SQ FT)
LOCATION A - IL 138 WEST			
IL 138 - MAINLINE			
STA 83+68 TO STA 98+63	1,495.00	2	99.67
STA 101+37 TO STA 112+63	1,126.00	2	75.07
LOCATION B - IL 138 EAST			
IL 138 - MAINLINE			
STA 124+82.17 TO STA 125+08.67 BK	26.50	1	0.88
STA 39+01.32 AH TO STA 4+33.84	3,467.48	1	115.58
LOCATION C - STAUNTON ROAD			
STAUNTON ROAD			
STA 70+42.00 TO STA 76+96.00	654.00	2	43.60
TOTAL			334.80

PLOT DATE = 10/24/2006  
 FILE NAME = c:\p\projects\652403\shsched.dgn  
 PLOT SCALE = 1/8"=1'-0" / IN.  
 USER NAME = laughlin-1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FAS 728 (IL 138) & FAU 8136 (STAUNTON ROAD)  
 SECTION D 6 RESURFACING 2007-1  
 MACOUPIN COUNTY  
 SCALE: VERT.      DRAWN BY  
 HORIZ.              CHECKED BY  
 DATE