

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	VARIOUS	30	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* VARIOUS
** D-6 TRAFFIC SIGNAL MOD 2004-2

CODE NO.	ITEM	UNIT	TOTAL	90% FED 10% STATE	90% FED 5% STATE 5% LOCAL	90% FED 5% STATE 5% LOCAL	90% FED 5% STATE 5% LOCAL	90% FED 6.7% STATE 3.3% LOCAL	90% FED 5% STATE 5% LOCAL	90% FED 7.5% STATE 2.5% LOCAL	90% FED 5% STATE 5% LOCAL	
				Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	
				<i>URBAN</i> HILLSBORO*								
				HILLSBORO HILLSBORO CHATHAM LITCHFIELD LITCHFIELD** LINCOLN LINCOLN*** CARLINVILLE								
81012800	CONDUIT IN TRENCH, 3" DIA. , PVC	FOOT	5				5					
81013000	CONDUIT IN TRENCH, 4" DIA. , PVC	FOOT	11				11					
81306100	JUNCTION BOX (SPECIAL)	EACH	2				2					
81400100	HANDHOLE	EACH	2				2					
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	69				69					
87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18, 3 PAIR	FOOT	42				42					
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	12						12			
88600100	DETECTOR LOOP, TYPE I	FOOT	523				523					
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2							2		
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4							4		
88040310	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-3 SECTION, 2-5 SECTION, BRACKET MOUNTED	EACH	4							4		
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	10	1	1	1	2		3	1	1	
89502350	REMOVE AND REINSTALL ELECTRIC CABLE ^{FROM} CONDUIT	FOOT	575				575					
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1						1			
89502380	REMOVE EXISTING HANDHOLE	EACH	2				2					

- * MAIN STREET & SCHOOL STREET
- ** IL. 16 & ST. FRANCIS
- *** LOGAN STREET & KEOKUK STREET

PLOT DATE : 10/24/2005
 FILE NAME : c:\p\proj\72885\72885.dgn
 PLOT SCALE : 2500:1
 USER NAME : laughtin1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE: _____

DRAWN BY: DAV
CHECKED BY: YTY

Rev.