

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	24TS-3	LOGAN	6	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

URBAN

LOCATION
IL 10
AT UNION ST.
IN LINCOLN
90% FEDERAL
5% STATE
5% CITY OF
LINCOLN
Y031-IF

Code No.	Item	Unit	Total	
67100100	MOBILIZATION	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7/C	FOOT	32	32
87502680	TRAFFIC SIGNAL POST, ALUMINUM, 14 FT.	EACH	2	2
87502690	TRAFFIC SIGNAL POST, ALUMINUM, 15 FT.	EACH	2	2
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	11	11
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8	8
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1
X0323153	ELECTRIC CABLE IN CONDUIT, GROUND, #6 1/C (GREEN)	FOOT	390	390
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4	4
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4	4
88040120	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED	EACH	2	2
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	2
88040250	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-4 SECTION BRACKET MOUNTED	EACH	2	2
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	4	4
88102830	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	2	2

PLT DATE : 10/25/2006
 FILE NAME : J:\6235291\10-25-06\10-25-06.dgn
 PLOT SCALE : 42.35291 / IN
 USER NAME : leahtlme1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**INDEX OF SHEETS, STANDARDS LIST,
 COMMITMENTS, & GENERAL NOTES**

SCALE: VERT.
 HORIZ.
 DATE 10-24-06

DRAWN BY: TMJ
 CHECKED BY: VTY