

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	(BX-1)TS-2	CLARK	8	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
• F.A.P. RTE. 332 AND F.A.S. RTE. 1707				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 90% FED. / 10% STATE Y031-1F
CODE NO	ITEM	UNIT		
* 42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH.	SO FT	189	189
* 44000600	SIDEWALK REMOVAL	SO FT	179	179
67100100	MOBILIZATION	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
* 72000100	SIGN PANEL - TYPE 1	SO FT	16	16
* 72000200	SIGN PANEL - TYPE 2	SO FT	28	28
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	194	194
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	110	110
81013200	CONDUIT IN TRENCH, 6" DIA., PVC	FOOT	10	10
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	269	269
81400100	HANDHOLE	EACH	4	4
81400300	DOUBLE HANDHOLE	EACH	1	1
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	314	314
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	234	234
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	845	845
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2225	2225
87502660	TRAFFIC SIGNAL POST, ALUMINUM 12 FT.	EACH	2	2
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	4	4
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	1	1

SUMMARY OF QUANTITIES (Cont'd)			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 90% FED. / 10% STATE Y031-1F
CODE NO	ITEM	UNIT		
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1	1
87700270	STEEL MAST ARM ASSEMBLY AND POLE, 46 FT.	EACH	2	2
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	18	18
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	50	50
87900200	DRILL EXISTING HANDHOLE	EACH	1	1
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4	4
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	5	5
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	3	3
88040290	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	1
88102810	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	EACH	2	2
88200410	TRAFFIC SIGNAL BACKPLATE, LOUVERED, FORMED PLASTIC	EACH	17	17
88800100	PEDESTRIAN PUSH-BUTTON	EACH	2	2
89502210	MODIFY EXISTING CONTROLLER CABINET	EACH	1	1
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1	1
X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	853	853

* SPECIALTY ITEMS

PLOT DATE = 10/12/2006
 FILE NAME = c:\p\proj\74209\081206\p01.dgn
 PLOT SCALE = 20.0000 / 1 IN.
 USER NAME = snc\jcm

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____