

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
789	54BR-1	MADISON	62	4
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 76864				

SUMMARY OF QUANTITIES			URBAN 80% FED 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		I000-2A	X071-2A	SFTY-3N
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70101205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	12	12		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	8124	6332	1792	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3640	2744	896	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	52	52		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2812	2214	598	
70400500	TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	1840	1840		
70400600	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	FOOT	1800	1800		
* 72000100	SIGN PANEL - TYPE 1	SQ FT	10	10		
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	24	24		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4682	4682		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	1456		1456	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	20		
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	6		6	
* 78200305	PRISMATIC BARRIER REFLECTOR	EACH	10		10	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	14	14		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	308	308		
X0301865	PIPE CULVERT REMOVAL 24"	FOOT	52.5	52.5		
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	648		648	
X0325213	COMPOSITE BRIDGE APPROACH PAVEMENT	SQ YD	249		249	
X0950100	PIPE CULVERT REMOVAL 15"	FOOT	71	71		
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1		1	
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	10	10		
X7200200	WIDE LOAD SIGNING	L SUM	1	1		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4		4	

SUMMARY OF QUANTITIES			URBAN 80% FED 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		I000-2A	X071-2A	SFTY-3N
* Z0065000	SETTING PILES IN ROCK	EACH	12		12	
XZ030260	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2			2
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	88		88	
© Z0076600	TRAINEES	HOUR	1500	1500		

PLOT DATE = 10/19/2006
 FILE NAME = c:\p\proj\54br\405\plan\shl405b.dgn
 SHEET = 4 OF 64
 REFERENCE = 48624

Rev.

* SPECIALTY ITEMS © 4080