



**BILL OF MATERIAL**

Bar	No.	Size	Length	Shape
h403(E)	24	#15	8.90 m	—
h404(E)	41	#15	9.60 m	—
u40(E)	153	#15	1.53 m	⌊
v405(E)	30	#15	0.97 m	—
v422(E)	34	#15	0.76 m	—
v423(E)	15	#15	3.46 m	—
v424(E)	15	#15	3.65 m	—
v425(E)	30	#15	3.97 m	—
v426(E)	30	#15	3.83 m	—
Concrete Structures		Cu. M	43.9	
Reinforcement Bars, Epoxy Coated		kg	1,940	
Structure Excavation		Cu. M	20.2	
Permanent Steel Sheet Piling		Sq. M	298	
Pipe Handrail		Meter	45	

**NOTES:**  
 See Sheet S16 for Notes.

SHEET S21 of S28

REVISIONS		NAME	DATE
NO.	DESCRIPTION		

**URS** 1701 GOLF ROAD, SUITE 1000 TEL (847) 228-0707  
 ROLLING MEADOWS, IL 60008 FAX (847) 228-1115

VILLAGE OF ADDISON  
**SALT CREEK GREENWAY TRAIL**  
 RET. WALL STA. 16+556 TO 16+583  
 PLAN & ELEVATION

DATE: 06/30/05 DRAWN BY: MDS  
 DESIGNED BY: MDS CHECKED BY: GAT