

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	0711 N-1	DuPAGE	54	3
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE		
				ROADWAY 70% FED 30% STATE 1000-2A	TRAFFIC SIGNAL 70% FED 20% STATE 10% ITASCA Y031-1F	INTERCONNECT 70% FED 30% STATE Y031-1F
20101000	TEMPORARY FENCE	FOOT	500	500		
20101100	TREE TRUNK PROTECTION	EACH	1	1		
* 20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	5	5		
* 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	5	5		
20200100	EARTH EXCAVATION	CU YD	1076	1076		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	982	982		
20700420	POROUS GRANULAR EMBANKMENT SUBGRADE	CU YD	290	290		
20800150	TRENCH BACKFILL	CU YD	210	210		
* 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5726	5726		
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	71	71		
* 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	71	71		
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	71	71		
* 25100630	EROSION CONTROL BLANKET	SQ YD	5937	5937		
* 25200110	SODDING, SALT TOLERANT	SQ YD	5726	5726		
* 25200200	SUPPLEMENTAL WATERING	UNIT	58	58		
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1680	1680		
* 28000300	TEMPORARY DITCH CHECK	EACH	4	4		
28000510	INLET FILTERS	EACH	7	7		
31101400	SUBBASE GRANULAR MATERIAL, TYPE B, 6"	SQ YD	2317	2317		
35300210	PORTLAND CEMENT CONCRETE BASE COURSE, 7 1/2"	SQ YD	11	11		
35300400	PORTLAND CEMENT CONCRETE BASE COURSE, 9"	SQ YD	965	965		
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	40	40		
35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	1003	1003		
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	44	44		
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	55	55		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2.7	2.7		
40600300	AGGREGATE (PRIME COAT)	TON	0.5	0.5		

CODE NO.	ITEM	UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE		
				ROADWAY 70% FED 30% STATE 1000-2A	TRAFFIC SIGNAL 70% FED 20% STATE 10% ITASCA Y031-1F	INTERCONNECT 70% FED 30% STATE Y031-1F
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	362	362		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT MIX ASPHALT SURFACE REMOVAL , BUTT JOINT	SQ YD	295	295		
40603510	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5	5		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	542	542		
42001300	PROTECTIVE COAT	SQ YD	1106	1106		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5"	SQ FT	4900	4900		
42400800	DETECTABLE WARNINGS	SQ FT	60	60		
44000100	PAVEMENT REMOVAL	SQ YD	521	521		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	4979	4979		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	586	586		
44000600	SIDEWALK REMOVAL	SQ FT	2925	2925		
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SQ YD	68	68		
44002224	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 6"	SQ YD	345	345		
44201976	CLASS D PATCHES, TYPE II	SQ YD	275	275		
44201978	CLASS D PATCHES, TYPE III	SQ YD	70	70		
44201980	CLASS D PATCHES, TYPE IV	SQ YD	149	149		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3879	3879		
48101500	AGGREGATE SHOULDERS, TYPE B, 6"	SQ YD	233	233		
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	140	140		
△ 55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100		
550A0050	STORM SEWERS, CLASS A, TYPE 1, 12"	FOOT	166	166		
550A0340	STORM SEWERS, CLASS A, TYPE 2, 12"	FOOT	142	142		
550A0380	STORM SEWERS, CLASS A, TYPE 2, 18"	FOOT	304	304		

* SPECIALTY ITEMS
 △ NON PARTICIPATING ITEMS, 100% STATE
 ** 100% VILLAGE OF ITASCA PARTICIPATION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.U. ROUTE 1321 (IL. ROUTE 19)
 IL. ROUTE 19
 SUMMARY OF QUANTITIES
 SCALE: N.T.S. DATE 11/21/06
 DRAWN BY ES
 CHECKED BY JIP

PLOT DATE = 11/21/06
 PLOT SCALE = AS SHOWN
 USER NAME = JIP