

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	0711 N-1	DUPAGE	54	4
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES		UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE		
CODE NO.	ITEM			ROADWAY 70% FED 30% STATE 1000-2A	TRAFFIC SIGNAL 70% FED 20% STATE 10% ITASCA Y031-1F	INTERCONNECT 70% FED 30% STATE Y031-1F
550A0680	STORM SEWERS, CLASS A, TYPE 3, 18"	FOOT	292	292		
550A0640	STORM SEWERS, CLASS A, TYPE 3, 12"	FOOT	165	165		
Δ 56400100	FIRE HYDRANTS TO BE MOVED	EACH	3	3		
60107600	PIPE UNDERDRAINS 4"	FOOT	122	122		
60201340	CATCH BASINS, TYPE A, 4' DIAMETER, TYPE 24 FRAME AND GRATE	EACH	6	6		
60218400	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5		
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	1	1		
* 60258000	MANHOLES TO BE RECONSTRUCTED (SPECIAL)	EACH	1	1		
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	1		
60266600	VALVE BOXES TO BE ADJUSTED	EACH	5	5		
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	8	8		
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	1	1		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3	3		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	769	769		
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1715	1715		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	5	5		
67100100	MOBILIZATION	L SUM	1	1		
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	107	107		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3721	3721		
* 72000200	SIGN PANEL - TYPE 2	SQ FT	43		43	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	108	108		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE, 4"	FOOT	6158	6158		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE, 6"	FOOT	665	665		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE, 12"	FOOT	126	126		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE, 24"	FOOT	103	103		

SUMMARY OF QUANTITIES		UNIT	TOTAL QTY.	CONSTRUCTION TYPE CODE		
CODE NO.	ITEM			ROADWAY 70% FED 30% STATE 1000-2A	TRAFFIC SIGNAL 70% FED 20% STATE 10% ITASCA Y031-1F	INTERCONNECT 70% FED 30% STATE Y031-1F
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	65	65		
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	26	26		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1892	1892		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	33	33		
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	683		495	188
* 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	201		201	
* 81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	29		29	
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	10		10	
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	46		46	
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	180		180	
* 81400100	HANDHOLE	EACH	4		4	
* 81400200	HEAVY-DUTY HANDHOLE	EACH	2		2	
* 81400300	DOUBLE HANDHOLE	EACH	1		1	
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	894		706	188
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2			2
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1		1	
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1		1	
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	595		595	
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1140		1140	
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1331		1331	
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	582		582	
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	973		973	
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	40		40	
* 87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT.	EACH	1		1	

* SPECIALTY ITEMS
 Δ NON PARTICIPATING ITEMS, 100% STATE
 ** 100% VILLAGE OF ITASCA PARTICIPATION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.U. ROUTE 1321 (IL. ROUTE 19)
 IL. ROUTE 19
 SUMMARY OF QUANTITIES
 SCALE: N.T.S.
 DATE 11/21/06
 DRAWN BY ES
 CHECKED BY JIP

PLOT DATE = 11/21/06
 FILE NAME = I:\CADD\19\Blomington\blomington\Proposed\Plans\Rev. Green\Cover\S00.dgn
 PLOT SCALE = #SCALE#
 USER NAME = #USER#