

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1321	0711 N-1	DuPAGE	54	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	

HMA SURFACE REMOVAL, VAR DEPTH	
LOCATION	QTY (SQ. YD)
IL 19	3573
BLOOMINGDALE RD.	916
TOTAL	4489

PROPOSED ROADWAY PAVEMENT					
LOCATION	HMA SURF. CRSE. MIX "D" NTO	LVL. BNDR (MM). NTO	PCC BASE COURSE, 9"	HMA BASE COURSE, 7"	SUBBASE GRAN MATERIAL, 6" TYPE B
IL 19	445 TONS	298 TONS	965 SQ YD	-	1087 SQ YD
BLOOMINGDALE RD.	97 TONS	64 TONS	-	1003 SQ YD	1230 SQ YD
TOTAL	542 TONS	362 TONS	965 SQ YD	1003 SQ YD	2317 SQ YD

COMB. CURB AND GUTTER		
LOCATION	B-6.24	B-6.12
IL 19	1663	180
BLOOMINGDALE RD.	52	589
TOTAL	1715	769

RAISED REFLECT. PAVE. MARKER			
LOCATION	PROP (EA.)	REMOVAL (EA.)	TEMP (EA.)
IL 19	42	33	26
BLOOMINGDALE RD.	23	0	-
TOTAL	65	0	26

PROPOSED PAVEMENT MARKINGS					
LOCATION	LETTER AND SYMBOLS (SQ FT)	LINE 4 IN (FT)	LINE 6 IN (FT)	LINE 12 IN (FT)	LINE 24 IN (FT)
IL 19	72	4185	403	91	70
BLOOMINGDALE RD.	36	1973	262	35	33
TOTAL	108	6158	665	126	103

AGG. SHLDRS, TYPE B, 6"	
LOCATION	QTY (SQ. YD.)
IL 19	233

HMA. SHOULDERS, 6"	
LOCATION	QTY (SQ. YD.)
IL 19	140

EARTHWORK					
	EARTH EX. (CU YD)	EMBANKMENT (CU YD)	ADJ. EARTH EX. (15%)	BALANCE WASTE (+) OR SHORTAGE (-)	UNSUITABLE (CU YD)
IL 19 - STAGE 1					
1001+79 TO 1005+00	110.6	0.0	94.0	+94.0	55.3
1005+00 TO 1009+00	131.1	0.0	111.4	+111.4	64.9
1009+00 TO 1011+88	196.2	49.7	166.8	+117.1	196.2
TOTAL	437.9	49.7	372.2	+322.5	316.4
IL 19 - STAGE 2					
1001+79 TO 1005+00	108.1	0.0	91.9	+91.9	123.1
1005+00 TO 1009+00	99.1	196.9	84.2	-112.6	168.9
1009+00 TO 1011+88	221.0	0.0	187.9	+187.9	137.6
TOTAL	428.2	196.9	364.0	+167.2	429.5
BLOOMINGDALE RD. - STAGE 1					
2003+06 TO 2007+64	210.3	316.8	178.8	-138.0	236.5
TOTAL	210.3	316.8	178.8	-138.0	236.5

EROSION CONTROL ITEMS			
LOCATION	TEMP. EROSION CONTROL SEEDING (POUND)	TEMPORARY DITCH CHECK (EA.)	SEDIMENT CONT., SILT FENCE (FOOT)
STAGE 1	1380	2	1760
STAGE 2	300	2	1023
TOTAL	1680	4	2783

FIRE HYDRANTS TO BE MOVED		
LOCATION	STATION	OFFSET
IL 19	1000+11	21' LT
IL 19	1004+83	77' RT
IL 19	1011+07	24' LT

GRAND TOTAL	1076			+351.7	982
--------------------	-------------	--	--	---------------	------------

PLOT DATE = 11/21/06
 FILE NAME = W:\PROJECTS\Bloomington\Bloomington\Proposed\Plans_Rev\Draw\Cover\INDEX-NOTES.dgn
 USER NAME = JUSER8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.U. ROUTE 1321 (IL. ROUTE 19)

**IL. ROUTE 19
 SCHEDULE OF QUANTITIES**

SCALE: NONE
 DATE 11/21/06

DRAWN BY ES
 CHECKED BY JJP