

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2796	(L,K)B	EFFINGHAM	35	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		Y007		
20100500	TREE REMOVAL, ACRES	ACRE	0.3	0.3		
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	11	11		
20400800	FURNISHED EXCAVATION	CU YD	1063	1063		
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1400	1400		
* 25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.7	0.7		
* 25100630	EROSION CONTROL BLANKET	SQ YD	280	280		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	140	140		
28000400	PERIMETER EROSION BARRIER	FOOT	450	450		
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	170	170		
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	240	240		
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	3	3		
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	220	220		
42001200	PAVEMENT FABRIC	SQ YD	220	220		
44000100	PAVEMENT REMOVAL	SQ YD	220	220		
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	50	50		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	990	990		
51500100	NAME PLATES	EACH	1	1		
54001000	BOX CULVERT END SECTIONS	EACH	2	2		
54011210	PRECAST CONCRETE BOX CULVERT 12' X 10'	FOOT	78	78		
54213447	END SECTIONS 12"	EACH	3	3		
60100945	PIPE DRAINS 12"	FOOT	40	40		
60403500	GRATES, TYPE B	EACH	3	3		
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	11	11		
60602800	CONCRETE GUTTER, TYPE B	FOOT	330	330		
60900515	CONCRETE THRUST BLOCKS	EACH	3	3		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	700	700		
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	3	3		
63200310	GUARDRAIL REMOVAL	FOOT	263	263		
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	6	6		
67100100	MOBILIZATION	L SUM	1	1		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	3	3		

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		Y007		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1200	1200		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	11	11		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3		
* A2002366	TREE, BETULA NIGRA (RIVER BIRCH), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	50	50		
* A2007612	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 1-1/2" CALIPER, BALLED AND BURLAPPED	EACH	50	50		
* B2001166	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	50	50		
X0324952	DETOUR SIGNING	L SUM	1	1		
X0545000	BOX CULVERT REMOVAL	FOOT	61	61		

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. / HORIZ. / DATE

DRAWN BY / CHECKED BY

PLOT DATE = 10/26/2006
 FILE NAME = c:\pcc\meta\94942\dl002a.dgn
 PLOT SCALE = 280000 / IN
 USER NAME = schaeferjm