

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2796	(L,K)B	EFFINGHAM	35	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

**GUARDRAIL SCHEDULE**

A=STEEL PLATE BEAM GUARDRAIL, TYPE A  
 B=GUARDRAIL REMOVAL  
 C=TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT)  
 D=TRAFFIC BARRIER TERMINAL, TYPE 2  
 H=GUARDRAIL MARKER, TYPE A  
 I=TERMINAL MARKER, DIRECT APPLIED

	A FT	B FT	C EACH	D EACH	H EACH	I EACH
LT STA 1220+34 TO STA 1225+34 RT STA 1219+55 TO STA 1222+80	400 300	263	2 1	1	6 5	2 1
<b>TOTALS</b>	700	263	3	1	11	3

**PIPE DRAIN SCHEDULE**

**GRATES, TYPE B**

RT STA 1220+68	1 EACH
LT STA 1221+44	1 EACH
LT STA 1223+82	1 EACH
<b>TOTAL</b>	<b>3 EACH</b>

**PIPE DRAINS 12"**

RT STA 1220+68	20 FEET
LT STA 1221+44	10 FEET
LT STA 1223+82	10 FEET
<b>TOTAL</b>	<b>40 FEET</b>

**CONCRETE THRUST BLOCKS**

RT STA 1220+68	1 EACH
LT STA 1221+44	1 EACH
LT STA 1223+82	1 EACH
<b>TOTAL</b>	<b>3 EACH</b>

**END SECTIONS 12"**

RT STA 1220+68	1 EACH
LT STA 1221+44	1 EACH
LT STA 1223+82	1 EACH
<b>TOTAL</b>	<b>3 EACH</b>

**EARTHWORK SCHEDULE**

LOCATION	EARTH EXCAVATION CU. YD.	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE CU. YD.	EMBANKMENT CU. YD.	EARTHWORK BALANCE WASTE(+) / SHORTAGE(-) CU. YD.
CUT SECTIONS	284	213		213
SHOULDER EXCAVATION	138	104		104
FILL SECTIONS		0	2430	-2430
EXCAVATION FOR BOX	1400	1050		1050
<b>TOTALS</b>	<b>1822</b>	<b>1367</b>	<b>2430</b>	<b>-1063</b>

**EXCAVATING AND GRADING EXISTING SHOULDER**

LT STA 1219+00 TO 1226+00	7 UNIT
RT STA 1219+00 TO 1222+75	4 UNIT
<b>TOTAL</b>	<b>11 UNIT</b>

**POROUS GRANULAR EMBANKMENT**

STA 1222+06 TO 1222+80 1400 C. Y.

**GUTTER SCHEDULE**

LOCATION	CLASS SI CONCRETE OUTLET CU. YD.	CONCRETE GUTTER TYPE B FOOT
RT STA 1219+09 TO 1219+22	0.66	
RT STA 1219+22 TO 1220+25		103
RT STA 1220+25 TO 1220+69	3.00	
LT STA 1219+88 TO 1220+00	0.66	
LT STA 1220+00 TO 1221+02		102
LT STA 1221+02 TO 1221+45	3.00	
LT STA 1223+81 TO 1224+25	3.00	
LT STA 1224+25 TO 1225+50		125
LT STA 1225+50 TO 1225+62	0.66	
<b>TOTALS</b>	<b>11.0</b>	<b>330</b>

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<b>SCHEDULES</b>

SCALE: VERT. / HORIZ. / DATE

DRAWN BY / CHECKED BY

PLOT DATE = 10/27/2006  
 FILE NAME = c:\pvc\projects\94942\cadd\0602.dgn  
 PLOT SCALE = 20.0000 / IN.  
 USER NAME = schaefer,jr