

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	3-2, 8X-1, 4-2	SALINE	233	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES
US 45 - IL 13 RELOCATION - CONTRACT 5

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	SALINE	
				ROAD FOUR LANE	TRAFFIC SIGNAL
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	3076	3076	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4,899	4,899	
44000600	SIDEWALK REMOVAL	SQ FT	12,156	12,156	
48100100	AGGREGATE SHOULDERS, TYPE A	TON	246	246	
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2	2	
50104400	CONCRETE HEADWALL REMOVAL	EACH	5	5	
50105220	PIPE CULVERT REMOVAL	FOOT	309	309	
50300225	CONCRETE STRUCTURES	CU YD	22.7	22.7	
50800105	REINFORCEMENT BARS	POUND	1,660	1,660	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	4	4	
54213666	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 21"	EACH	1	1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	3	3	
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4	4	
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	8	8	
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	4	4	
54248515	CONCRETE COLLAR	EACH	2	2	
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	129	129	
542A1075	PIPE CULVERTS, CLASS A, TYPE 2 30"	FOOT	44	44	
542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	513	513	
542A1087	PIPE CULVERTS, CLASS A, TYPE 2 42"	FOOT	154	154	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	3,195	3,195	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	517	517	
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	2,676	2,676	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	1,042	1,042	
550A0430	STORM SEWERS, CLASS A, TYPE 2 30"	FOOT	324	324	
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	392	392	
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	72	72	
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	366	366	
55100100	STORM SEWERS REMOVAL 4"	FOOT	12	12	
55100500	STORM SEWERS REMOVAL 12"	FOOT	406	406	
55100700	STORM SEWERS REMOVAL 15"	FOOT	120	120	
55100900	STORM SEWERS REMOVAL 18"	FOOT	528	528	
55101100	STORM SEWERS REMOVAL 21"	FOOT	31	31	
55101600	STORM SEWERS REMOVAL 36"	FOOT	421	421	
60218400	MANHOLES TYPE A, 4' DIA TYPE 1 FRAME CLOSED LID	EACH	3	3	
60221100	MANHOLES TYPE A, 5' DIA TYPE 1 FRAME CLOSED LID	EACH	1	1	
60221700	MANHOLES, TYPE A, 5' DIAMETER, TYPE 8 GRATE	EACH	1	1	
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	5	5	

DRAWN BY JS
 CHECKED BY DB

M:\PROJECTS\PROJ3526\ROADWAY\COMMON\ACTIVE FILES
 SUMO1-3526C5.DGN
 Reference Files