

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	3-2, 8X-1, 4-2	SALINE	233	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SUMMARY OF QUANTITIES US 45 - IL 13 RELOCATION - CONTRACT 5		COUNTY:		SALINE URBAN	
		LOCATION:	CONSTRUCTION TYPE CODE:	1000-2A	Y031-1F
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROAD FOUR LANE	TRAFFIC SIGNAL
78300105	PAVEMENT MARKING REMOVAL	FOOT	200	200	
80300100	LOCATING UNDERGROUND CABLE	FOOT	2150		2150
80500105	SERVICE INSTALLATION TYPE A (MODIFIED)	EACH	2		2
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	1480		1480
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	355		355
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	35		35
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	70		70
81021540	CONDUIT, AUGERED, 1 1/2" DIA., PVC	FOOT	325		325
81021550	CONDUIT, AUGERED, 2" DIA., PVC	FOOT	210		210
81021560	CONDUIT, AUGERED, 2 1/2" DIA., PVC	FOOT	25		25
81021570	CONDUIT, AUGERED, 3" DIA., PVC	FOOT	465		465
81021590	CONDUIT, AUGERED, 4" DIA., PVC	FOOT	210		210
81400100	HANDHOLE	EACH	8		8
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2255		2255
82103900	LUMINAIRE, SODIUM VAPOR, MULTIMOUNT, 250 WATT	EACH	8		8
82500605	LIGHTING CONTROLLER - PHOTOCCELL RELAY	EACH	2		2
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2		2
81500100	GULFBOX JUNCTION	EACH	17		17
* 87301245	ELECTRIC CABLE IN CONDUIT SIGNAL NO. 14 5C	FOOT	250		250
87301255	ELECTRIC CABLE IN CONDUIT SIGNAL NO. 14 7C	FOOT	1990		1990
87301275	ELECTRIC CABLE IN CONDUIT SIGNAL NO. 14 12C	FOOT	1905		1905
87301305	ELECTRIC CABLE IN CONDUIT LEAD-IN, NO. 14, 1 PAIR	FOOT	9045		9045
87502310	TRAFFIC SIGNAL POST, PAINTED STEEL 16 FT	EACH	5		5
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT	EACH	2		2
87700260	STEEL MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	2		2
87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1		1
87702930	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 40 FT	EACH	2		2
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 44 FT.	EACH	1		1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	17.5		17.5
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	7		7
87800400	CONCRETE FOUNDATION, TYPE E, 30-INCH DIAMETER	FOOT	120		120
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	3		3
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8		8
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	13		13
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	6		6
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	16		16
88500100	INDUCTIVE LOOP DETECTOR	EACH	18		18

\* SPECIALTY ITEMS

SUMMARY OF QUANTITIES

DRAWN BY JS  
CHECKED BY DB

PROJECT: C:\PROJ\3526\ROADWAY\COMMON\3526\3526.DGN  
DATE: 10/13/2006 2:28:54 PM