CONTRACT NO. 98627

FAP RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	3-2, 8X-1, 4-2	SALINE	233	65
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PROP. R.O.W.
EXIST. R.O.W.
EXIST. ℄ ILL. 34 (MAIN ST.)
2 CENTERED CURVE
85'-300'
10' OFFSET
COMBINATION CONCRETE CURB AND GUTTER, TYPE M6-06 (TYP.)
CONCRETE MEDIAN SURFACE, 4" (TYP.)
1038+20.38
33.00' LT
1040+16.56
45.00' LT
1039+02.84 PROP. ℄ ILL. 13 RELOCATION
1671+87.02 EXIST. ℄ ILL. 34 (MAIN ST.)
PROP. ℄ ILL. 13 RELOCATION
1038+36.60
3.00' LT
1039+69.10
3.00' RT
1039+85.24
33.00' RT
PI STA. 1672+08.30
OVERHEAD SIGN
36" RCP
W.M.
HANDICAPPED RAMP (TYP)
RAMPED MEDIAN NOSE (TYP)
CONCRETE MEDIAN, TYPE SB-6.24 (SPECIAL) (TYP.)
END PCC PAVEMENT (OPTION 1 ONLY)
1041+46.05
2 CENTERED CURVE
85'-300'
10' OFFSET
COMBINATION CONCRETE CURB AND GUTTER, TYPE M6-24 (TYP.)
PROP. R.O.W.
AGG
NOTE:
FOR INTERSECTION GEOMETRY SEE GEOMETRICS SHEET 118.
NOTE:
FOR ILL. 34 & MAIN ST. PLAN/PROFILE SEE SHEETS 74 & 75.
ASPH
ROAD CLOSED
1041+46.05
45.00' LT
BEGIN TAPER
PCC SIDEWALK, 4"
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (TYP.)
CONSTRUCTION LIMITS
SCALE: 1"= 20'
1043+46.05
33.00' LT
END TAPER
1041+54.10
3.00' RT
BEGIN TAPER
PC STA 1041+42.70
+71.40
CURVE 21
1043+54.10
9.00' LT
END TAPER
PT STA 1043+94.95
COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (TYP.)
CONCRETE MEDIAN SURFACE, 4"
CONSTRUCTION LIMITS
ROAD CLOSED
VINE ST.
CHERRY ST.
TEMP. EASEMENT

B.M. 304 "□" CUT END A.R.C.
WEST SIDE OF RTE. 34
STA. 1038±60, 35' RT. CENTERLINE
EL. 363.44

℄ ILL. 34 (MAIN ST.)
+75.00 EL. 364.88
1038+25.00 RT
363.30
-0.52% RT
PROP. RIGHT DITCH
PROP. PROFILE GRADE ILL. 13 RELOCATION
EXIST. PROFILE GRADE
1040+25.00 RT
364.50
1040+25.00 LT
364.00
-0.53% RT
-0.46% LT
1041+20.00 RT
364.00
+70.00 EL. 366.35
+0.50% RT
+0.41% LT
1041+40.00 LT
363.45
160.00' V.C.
VPI STA. 1042+50.00
EL. 366.75
+0.50%
-0.49%
1042+00.00 RT
364.40
1042+00.00 LT
363.70
-1.82% LT
-2.00% RT
1042+50.00 RT
363.40
1042+50.00 LT
362.79
+30.00 EL. 366.36
-0.50% RT
-0.51% LT
PROP. RIGHT DITCH
PROP. LEFT DITCH

1038+00	1038+50	1039+00	1039+50	1040+00	1040+50	1041+00	1041+50	1042+00	1042+50	1043+00	1043+50	1044+00
364.16 / 364.69	363.75 / 364.77	364.10 / 365.00	363.84 / 365.25	364.21 / 365.50	364.33 / 365.75	364.37 / 366.00	364.56 / 366.25	364.55 / 366.47	363.87 / 366.55	363.34 / 366.48	363.67 / 366.26	362.27 / 366.02

PLAN PROFILE – STA. 1038+00.00 TO STA. 1044+00.00

\plan_and_profile\pp20c5-04.dgn 10/9/2006 12:27:04 PM