CONTRACT NO. 98961

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
328	*	WAYNE & WHITE	15	3
STA. 448+99		TO STA. 61+90		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (104,105)RS-4,(108)RS-3

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	WAYNE CO.	WHITE CO.		
			LOCATION:	RURAL			
			FUNDING:	80% FED / 20% STATE			
			WORK TYPE:	ROADWAY	BRIDGE	ROADWAY	GUARDRAIL
			CONST TYPE:	I000	SFTY-2A	I000	SFTY-3J
X0322729	MATERIAL TRANSFER DEVICE	TON	15913	452		15461	
Z0055300	RUMBLE STRIP	EACH	3			3	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	585	34		551	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	34281	968	56	33257	
40600300	AGGREGATE (PRIME COAT)	TON	571	16	2	553	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	25	1		24	
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	7957	226		7731	
40600895	CONSTRUCTING TEST STRIP	EACH	1			1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	494	43	346	105	
40600990	TEMPORARY RAMP	SQ YD	1176	15	160	1001	
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	15939	452	26	15461	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	87	5		82	
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	312		312		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	166319	5376		160943	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	26207			26207	
44201798	CLASS D PATCHES, TYPE I, 13 INCH	SQ YD	51			51	
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	575			575	
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	27			27	
44201847	CLASS D PATCHES, TYPE I, 17 INCH	SQ YD	47			47	
44201851	CLASS D PATCHES, TYPE II, 17 INCH	SQ YD	1554			1554	
44201855	CLASS D PATCHES, TYPE III, 17 INCH	SQ YD	60			60	
44201857	CLASS D PATCHES, TYPE IV, 17 INCH	SQ YD	174			174	
44201871	CLASS D PATCHES, TYPE I, 19 INCH	SQ YD	28	28			
44201875	CLASS D PATCHES, TYPE II, 19 INCH	SQ YD	51	45		6	
44201879	CLASS D PATCHES, TYPE III, 19 INCH	SQ YD	20	20			

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	WAYNE CO.	WHITE CO.		
			LOCATION:	RURAL			
			FUNDING:	80% FED / 20% STATE			
			WORK TYPE:	ROADWAY	BRIDGE	ROADWAY	GUARDRAIL
			CONST TYPE:	I000	SFTY-2A	I000	SFTY-3J
44201881	CLASS D PATCHES, TYPE IV, 19 INCH	SQ YD	27	27			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	131262	3722		127540	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2504	71		2433	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	390	23		367	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2				2
63200310	GUARDRAIL REMOVAL	FOOT	50				50
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7			7	
67100100	MOBILIZATION	L SUM	1			1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1			1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1			1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	9	4.5		4.5	
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	19692	564		19128	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	165681	7604		158077	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	190			190	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	157			157	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	37			37	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2188	63		2125	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	165681	7604		158077	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	190			190	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	157			157	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	37			37	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	821	23	3	795	
* 78201000	TERMINAL MARKERS - DIRECT APPLIED	EACH	2				2
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	821	23	3	795	
* 88600100	DETECTOR LOOP, TYPE I	FOOT	146		146		

*SPECIALTY ITEMS

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = 10/15/2020
FILE NAME = c:\pw_work\d98216*\d9821605-sht-sum.dgn
PLOT SCALE = 100.0000 ' / IN.
USER NAME = stevenpg

SUMMARY OF QUANTITIES