

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
873	128-51TS-3	FRANKLIN	6	3

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	URBAN CONSTRUCTION TYPE CODE Y031-F 100 % STATE	
		UNIT	TOTAL QUANTITIES
* 44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	213
* 60618300	CONCRETE MEDIAN SURFACE 4"	SQ FT	197
67100100	MOBILIZATION	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
80300100	LOCATING UNDERGROUND CABLE	FOOT	60
81012700	CONDUIT IN TRENCH, 2 1/2" DIA., PVC	FOOT	366
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	16
81021560	CONDUIT, AUGERED, 2 1/2" DIA., PVC	FOOT	191
81400100	HANDHOLE	EACH	4
81500100	GULFBOX JUNCTION	EACH	2
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	382
85700648	FULL-ACTUATED CONTROLLER, STANDARD SEQUENCE IV, 8 PHASES	EACH	1
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5/C	FOOT	688
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7/C	FOOT	326
87301305	ELECTRIC CABLE IN CONDUIT, LEAD IN, NO. 14 1 PAIR	FOOT	1131
87301855	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 8 2C	FOOT	34
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3
87900100	DRILL EXISTING FOUNDATION	EACH	6
88500100	INDUCTIVE LOOP DETECTOR	EACH	3
88600100	DETECTOR LOOP, TYPE I	FOOT	428
89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	1
89501150	RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1
89502380	REMOVE EXISTING HANDHOLE	EACH	4
X0301576	COAXIAL CABLE IN CONDUIT	FOOT	109
X0962500	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	L SUM	1
XX004683	RELOCATE EXISTING TRAFFIC SIGNAL CONTROLLER AND CABINET COMPLETE	EACH	1

* SPECIALTY ITEMS