

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	*	**	4	4
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. _____		ILLINOIS FED. AID PROJECT		

* D-9 SAFETY FY 07-2
 ** UNION AND ALEXANDER

GUARDRAIL SCHEDULE

LOCATION STATION TO STATION	GUARDRAIL REMOVAL FOOT	SPBGR TYPE A FOOT	TRAFFIC BARRIER TERMINAL		TERMINAL MARKERS DIRECT APPLIED EACH	GUARDRAIL MARKERS TYPE A EACH	REMARKS
			TY 1, SPL (TAN) EACH	TYPE 2 EACH			
UNION COUNTY							
091-0001 MEDIAN APPROACH							
RT 3041+24.00 TO RT 3042+45.00	121.0						REMOVAL
RT 3041+24.00 TO RT 3044+74.00		350.0					NEW SPBGR
RT 3044+74.00 TO RT 3045+24.00			1		1	8	NEW TERMINAL
091-0002 MEDIAN APPROACH							
LT 3034+65.00 TO LT 3035+15.00							
LT 3035+15.00 TO LT 3038+65.00		350.0	1		1	1	NEW TERMINAL
LT 3037+39.00 TO LT 3038+65.00	132.0					8	NEW SPBGR
ALEXANDER COUNTY							
002-0023 OUTSIDE DEPARTURE							
LT 1085+50.00 TO LT 1086+00.00				1			
LT 1086+00.00 TO LT 1087+50.00		160.0				1	NEW TERMINAL
LT 1087+25.00 TO LT 1087+50.00	25.0					4	NEW SPBGR
002-0024 OUTSIDE APPROACH							
RT 1086+87.50 TO RT 1088+37.50							REMOVAL
RT 1086+37.50 TO RT 1088+75.00		237.5	1		1	1	NEW TERMINAL
RT 1088+50.00 TO RT 1088+75.00	25.0					5	NEW SPBGR
002-0024 MEDIAN APPROACH							
LT 1085+52.00 TO LT 1086+02.00							
LT 1086+02.00 TO LT 1089+27.00		325.0	1		1	1	NEW TERMINAL
LT 1088+40.00 TO LT 1089+27.00	87.0					7	NEW SPBGR
002-0025 OUTSIDE APPROACH							
LT 1033+80.00 TO LT 1034+05.00	25.0						REMOVAL
LT 1033+30.00 TO LT 1035+92.50		212.5				5	NEW SPBGR
LT 1035+92.50 TO LT 1035+42.50			1		1	1	NEW TERMINAL
002-0025 OUTSIDE APPROACH							
RT 1025+42.50 TO RT 1025+92.50							
RT 1025+92.50 TO RT 1028+05.00		212.5	1		1	1	NEW TERMINAL
RT 1027+80.00 TO RT 1028+05.00	25.0					5	NEW SPBGR
002-0025 MEDIAN APPROACH							
RT 1030+70.00 TO RT 1030+82.50							
RT 1030+82.50 TO RT 1034+82.50		400.0		1			NEW TERMINAL
RT 1034+82.50 TO RT 1035+32.50						8	NEW SPBGR
RT 1030+20.00 TO RT 1032+30.00	210.0		1		1	1	NEW TERMINAL
002-0001 MEDIAN APPROACH							
RT 966+65.00 TO RT 967+18.00	53.0						REMOVAL
RT 966+65.00 TO RT 969+15.00		250.0				6	NEW SPBGR
RT 969+15.00 TO RT 969+65.00			1		1	1	NEW TERMINAL
002-0001 OUTSIDE APPROACH							
LT 966+47.00 TO LT 966+72.00	25.0						REMOVAL
LT 966+47.00 TO LT 968+47.50		200.5				5	NEW SPBGR
LT 968+47.50 TO LT 968+97.50			1		1	1	NEW TERMINAL
TOTALS:	728.0	2688.0	10.0	1.0	10.0	71.0	

PLOT DATE = 11/14/2006
 USER NAME = shapardg
 USER NAME = shapardg
 USER NAME = shapardg