CONTRACT NO. 99274

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9545	03-00133-00-RP	SALINE	43	3
SALINE COUNTY		LIBERTY ROAD		

SUMMARY OF QUANTITIES

J000-2A

CODE NO.	PAY ITEM	UNIT	QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	268
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	770
20200100	EARTH EXCAVATION	CU YD	3,500
20800150	TRENCH BACKFILL	CU YD	650
* 25000900	SEEDING, CLASS 1 (SPECIAL)	ACRE	1.3
25100630	EROSION CONTROL BLANKET	SQ YD	6,300
* 28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	175
28000300	TEMPORARY DITCH CHECKS	EACH	7
28000400	PERIMETER EROSION BARRIER	FOOT	2,000
28000500	INLET AND PIPE PROTECTION	EACH	55
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	2,800
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	500
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	520
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	106
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	1
54213699	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 54"	EACH	1
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1114
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	805
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	551
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	130
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	182
550A0180	STORM SEWERS, CLASS A, TYPE 1 42"	FOOT	33
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	312
550A0200	STORM SEWERS, CLASS A, TYPE 1 54"	FOOT	163
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	530
55100300	STORM SEWER REMOVAL 8"	FOOT	20
55100500	STORM SEWER REMOVAL 12"	FOOT	576
55100700	STORM SEWER REMOVAL 15"	FOOT	53
55100900	STORM SEWER REMOVAL 18"	FOOT	40
△ *56100500	WATER MAIN 4"	FOOT	335
△ *56200200	WATER SERVICE LINE 3/4"	FOOT	175
*60240200	INLETS, TYPE A, SPECIAL	EACH	6
*60243300	INLETS, SPECIAL, TYPE 3, 5'	EACH	46
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12
67100100	MOBILIZATION	L SUM	1
△ 72000100	SIGN PANEL – TYPE 1	SQ FT	19
△ 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	83.0
△ 78001110	PAINT PAVEMENT MARKING – LINE 4"	FOOT	900
△ 78001150	PAINT PAVEMENT MARKING – LINE 12"	FOOT	27
*LR420125	PORTLAND CEMENT CONCRETE PAVEMENT 7" (SPECIAL) WITH INTEGRAL CURB	SQ YD	12,600

CODE NO.	PAY ITEM	UNIT	QUANTITY
△ *XX004382	FLUSHING HYDRANT	EACH	2
△ *XX005891	WATER SERVICE RECONNECTIONS	EACH	4
△ *XX005796	TAPPING VALVES AND SLEEVES 3"	EACH	4
△ *XX005889	12" PVC WATERMAIN ENCASEMENT	FOOT	36
△ *XX005990	DETECTION WIRE	FOOT	510
*X0488100	SEPTIC TANK REMOVAL	EACH	1

△ SPECIALTY ITEMS

06 Nov 2006 – 7:30am X:\2003\03060\ac\plans\3-7summary and schedules.dwg