

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9545	03-00133-00-RP	SALINE	43	4
SALINE COUNTY		CLEVELAND STREET		

CONTRACT NO. 99274

### DRIVEWAY PAVEMENT SCHEDULE

* LOCATION	EXIST. SURFACE	DRIVEWAY PAVT. REMOVAL			PCC DRIVEWAY PAVT. 6"		
		LENGTH	WIDTH	SQ. YD.	LENGTH	WIDTH	SQ. YD.
50+42 RT	AGG.	-	-	-	9.4'	12'	15.3
51+32 LT	AGG.	-	-	-	9.4'	12'	15.3
52+54 LT	AGG.	-	-	-	9.4'	12'	15.3
52+67 RT	AGG.	-	-	-	9.4'	12'	15.3
52+90 RT	AGG./CONC.	8.6	10.8	10.1	9.4'	24'	27.9
54+18 LT	AGG.	-	-	-	9.4'	12'	15.3
55+20 RT	AGG.	-	-	-	9.4'	12'	15.3
56+05 LT	NONE	-	-	-	9.4'	12'	15.3
56+42 LT	AGG.	-	-	-	9.4'	12'	15.3
56+49 LT	NONE	-	-	-	9.4'	12'	15.3
56+50 RT	AGG.	-	-	-	9.4'	12'	15.3
57+48 RT	AGG.	-	-	-	9.4'	12'	15.3
59+95 RT	AGG.	-	-	-	9.4'	12'	15.3
62+72 LT	BIT.	17	20	37.8	9.4'	20'	23.7
63+41 LT	BIT.	15.5	20.2	34.8	9.4'	20'	23.7
63+71 RT	AGG.	-	-	-	9.4'	20'	23.7
64+83 RT	AGG.	-	-	-	9.4'	12'	15.3
65+55 RT	AGG.	-	-	-	9.4'	12'	15.3
66+80 RT	AGG.	-	-	-	9.4'	12'	15.3
67+88 RT	AGG.	-	-	-	9.4'	12'	15.3
70+09 RT	AGG.	-	-	-	9.4'	12'	15.3
70+39 RT	AGG.	-	-	-	9.4'	12'	15.3
72+03 LT	NONE	-	-	-	9.4'	12'	15.3
73+26 RT	AGG.	-	-	-	9.4'	12'	15.3
78+08 RT	AGG.	-	-	-	9.4'	12'	15.3
79+64 RT	NONE	-	-	-	9.4'	20'	23.7
80+75 RT	AGG.	-	-	-	9.4'	12'	15.3
81+82 RT	CONC.	15	13.9	23.2	9.4'	12'	15.3
82+58 RT	NONE	-	-	-	9.4'	12'	15.3
82+91 RT	AGG.	-	-	-	9.4'	12'	15.3

TOTAL DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT 105.9 505.2

\* EXACT LOCATION TO BE DESIGNATED BY THE ENGINEER

### PAINT PAVEMENT MARKING LINE (FEET)

LOCATION	CROSSWALK 6" WHITE	STOP BAR 12" WHITE	SKIP DASH 4" YELLOW
CENTERLINE 49+33 TO 84+70	-	-	900'
STA. 62+88 TO 63+00, 22' RT	-	12'	-
STA. 67+53 TO 67+68, 22' LT	-	15'	-
<b>TOTAL PAVEMENT MARKING</b>	<b>-</b>	<b>27'</b>	<b>900'</b>

### SIGNING SCHEDULE

APPROXIMATE LOCATION	TYPE	NO.	SIGN SQ. FT.	POSTS FOOT
52+00, 17'LT	NO PARKING	R7-(12X18)	1.50	13.5
55+50, 17'RT	NO PARKING	R7-(12X18)	1.50	13.5
63+05, 23'RT	STOP	R1-1 (30")	6.25	14.5
67+58, 24'LT	STOP	R1-1 (30")	6.25	14.5
69+00, 17'LT	NO PARKING	R7-(12X18)	1.50	13.5
84+10, 17'RT	NO PARKING	R7-(12X18)	1.50	13.5
<b>TOTAL SIGN AND POST QUANTITIES</b>			<b>18.5</b>	<b>83.0</b>

### WATER SERVICE LINE 3/4"

LOCATION	FOOT
55+70 WEST	55
75+00 EAST	10
75+50 WEST	90
76+00 EAST	20

TOTAL QUANTITIES 175

### PCC PAVEMENT 7" SPECIAL W/IC

LOCATION	AREA (SQ. YD.)
LIBERTY ROAD MAINLINE 49+66 TO 84+70	12,133
GIBBONS ROAD INTERSECTION	69
OLD CAIN ROAD INTERSECTION	167
ENTRANCE AT STA. 75+98 (LT)	231
<b>TOTAL PCC PAVEMENT 7" SPECIAL W/IC</b>	<b>12,600</b>