ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9545	03-00133-00-RP	SALINE	43	16
SALINE COUNTY		LIBERTY ROAD		

CONTRACT NO. 99274

LIBERTY BAPTIST CHURCH
(BILL CUMMINS, TRUSTEE*)

STRUCTURE NO. 21
INLET SPECIAL, TYPE A
TYPE 3V, F & G
STATION 63+15, 14.58' LT
LID ELEV. = 429.44
INV. ELEV. = 426.44

PROPOSED 20' ENTRANCE
EXISTING ASPHALT ENTRANCE
EXISTING R-O-W
CONCRETE HEADWALLS TO BE REMOVED
P.O.T. STA. 63+50.76 DEFLECT RIGHT 00°17'47"

STRUCTURE NO. 23
INLET SPECIAL, TYPE A
TYPE 3V, F & G
STATION 64+50, 14.58' LT
LID ELEV. = 427.25
INV. ELEV. = 424.25

EXISTING TOP OF BACKSLOPE

STRUCTURE NO. 22
INLET SPECIAL, TYPE 3, 5 FT.
STATION 63+15, 16.83' RT
LID ELEV. = 429.44
INV. ELEV. = 426.29

STORM SEWERS, CLASS 'A'
TYPE 1, 12" x 29'

STORM SEWERS, CLASS 'B'
TYPE 1, 12" x 130'

STORM SEWERS, CLASS 'A'
TYPE 1, 12" x 29'

STRUCTURE NO. 24
INLET SPECIAL, TYPE 3, 5 FT.
STATION 64+50, 16.83' RT
LID ELEV. = 427.25
INV. ELEV. = 424.10

STORM SEWERS, CLASS 'B'
TYPE 1, 12" x 145'

REMOVE EXISTING RETAINING WALL
REMOVE EXISTING BRICK SIDEWALK
TEMPORARY CONSTRUCTION EASEMENT
EXISTING 3" A.C. WATERMAIN
EXISTING GRAVEL DRIVE
GIBBONS ROAD
STOP BAR
RADIUS PT. STA. 62+63 30' RT
RADIUS PT. STA. 63+13 30' RT
DITCH CHECK
OMER L. & WILMA F. STONE
ROGER, JERRY & IRENE LANGFORD

62+50 63+00 63+50 64+00 64+50 65+00

℄ GIBBONS ROAD

HORIZONTAL 0 10 20
VERTICAL 0 5 10

Proposed Centerline Profile
Existing Centerline Profile

VERTICAL CURVE #5
L = 200'
VPC STA. 62+50 ELEV. 429.75
VPI STA. 63+50 ELEV. 429.25
VPT STA. 64+50 ELEV. 427.05
g5 = -0.50%
g6 = -2.20%

g6 = -2.20%

STORM SEWER, CLASS 'A' TYPE 1, 12" x 132'
STORM SEWER, CLASS 'A' TYPE 1, 12" x 145'
EXISTING GAS SERVICE ELEV. UNKNOWN

	62+50	63+00	63+50	64+00	64+50	65+00
Exist.	430.53	430.52	429.69	428.40	427.12	425.81
Prop.	429.75	429.39	428.83	428.04	427.05	425.95

430 425 420

03 Nov 2006 - 4:26pm X:\2003\03060\ac\plans\10-25plan & profile.dwg: Layout Tab '62+50'

BROWN & ROBERTS, INC

STATION 62+50 TO 65+00