

UN046

K:\Champaign\1060906\Draw\Sheets\
 FILE: 2 IDXSUM.dwg
 LAYOUT: 2 IDXSUM
 UPDATE BY: msmejkal
 SURVEY BOOK #
 DATE: Thu 11/16/06 4:31pm
 XREF DWG: Cintinfo.dwg

REVISIONS

NUMBER	BY	DATE




THIS BAR IS EQUAL TO 2"
 AT FULL SCALE (34x22).

INDEX TO SHEETS	
1	COVER SHEET
2	INDEX TO SHEETS / SUMMARY OF QUANTITIES
3	GENERAL NOTES
4	PROJECT SITE PLAN
5	CONSTRUCTION ACTIVITY PLAN
6	EXISTING CONDITIONS / REMOVAL PLAN
7	PAVING AND DRAINAGE PLAN
8	ELECTRICAL AND PAVEMENT MARKING PLAN
9	TYPICAL SECTIONS
10	STAKING PLAN
11	STORM SEWER PROFILES
12	EROSION CONTROL AND LANDSCAPING PLAN
13	EROSION CONTROL DETAILS
14	DRAINAGE DETAILS
15	ELECTRICAL AND WATER MAIN DETAILS
16	CROSS SECTIONS
17	FENCE DETAILS

SUMMARY OF QUANTITIES						
ITEM NO.	ITEM DESCRIPTION	UNIT	F/S/L QUANTITY	LOCAL ONLY QUANTITY	TOTAL QUANTITY	RECORD QUANTITY
AR106900	REMOVE LIGHT POLE	EA	2.00	-	2.00	
AR108158	1/C #8 5 KV UG CABLE IN UD	LF	350.00	-	350.00	
AR110214	4" STEEL DUCT, DIRECT BURY	LF	200.00	-	200.00	
AR110550	SPLIT DUCT	LF	30.00	-	30.00	
AR125410	MITL - STAKE MOUNTED	EA	2.00	-	2.00	
AR125901	REMOVE STAKE MOUNTED LIGHT	EA	3.00	-	3.00	
AR150510	ENGINEER'S FIELD OFFICE	LS	1.00	-	1.00	
AR152410	UNCLASSIFIED EXCAVATION	CY	1425.00	-	1425.00	
AR152442	OFFSITE BORROW EXCAVATION	CY	450.00	-	450.00	
AR156510	SILT FENCE	LF	790.00	-	790.00	
AR162960	RELOCATE CLASS E FENCE	LF	70.00	-	70.00	
AR162962	RELOCATE GATE - 24'	EA	1.00	-	1.00	
AR209606	CRUSHED AGG. BASE COURSE - 6"	SY	-	1830.00	1830.00	
AR209610	CRUSHED AGG. BASE COURSE - 10"	SY	3210.00	-	3210.00	
AR401610	BITUMINOUS SURFACE COURSE	TON	760.00	430.00	1190.00	
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	660.00	-	660.00	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	SY	95.00	-	95.00	
AR501900	REMOVE PCC PAVEMENT	SY	2720.00	-	2720.00	
AR602510	BITUMINOUS PRIME COAT	GAL	800.00	455.00	1255.00	
AR603510	BITUMINOUS TACK COAT	GAL	240.00	140.00	380.00	
AR620520	PAVEMENT MARKING - WATERBORNE	SF	885.00	-	885.00	
AR701412	12" RCP, CLASS III	LF	75.00	-	75.00	
AR701415	15" RCP, CLASS III	LF	355.00	-	355.00	
AR701424	24" RCP, CLASS III	LF	405.00	-	405.00	
AR701900	REMOVE PIPE	LF	205.00	-	205.00	
AR705524	4" PERFORATED UNDERDRAIN W/SOCK	LF	645.00	-	645.00	
AR751410	INLET	EA	2.00	-	2.00	
AR751540	MANHOLE 4'	EA	3.00	-	3.00	
AR751550	MANHOLE 5'	EA	3.00	-	3.00	
AR751560	MANHOLE 6'	EA	1.00	-	1.00	
AR760965	RELOCATE FIRE HYDRANT	EA	1.00	-	1.00	
AR800868	SOIL GUARD	SY	1025.00	-	1025.00	
AR901510	SEEDING	AC	0.90	-	0.90	
AR908510	MULCHING	AC	0.80	-	0.80	

UNIVERSITY OF ILLINOIS
 WILLARD AIRPORT
 CONSTRUCT N.E. T-HANGAR PAVEMENT
 INDEX TO SHEETS /
 SUMMARY OF QUANTITIES

© Copyright CMT, Inc.

CMT
 CRAWFORD, MURPHY & TILLY, INC.
 CONSULTING ENGINEERS
 License No. 164-000613

DESIGN BY: MJS
 DRAWN BY: MJS
 CHECKED BY: MJS
 APPROVED BY:
 DATE: 11/16/2006
 JOB No: 0505906
 A.I.P. PROJECT: 3-17-0016-23
 I.L. PROJ: CMI-3651
 SHEET 2 OF 17 SHEETS