



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 10, 2018

SUBJECT: FAP Route 343 (IL 681 (Dundee Rd))  
Project NHPP-B1GJ(286)  
Section 30T-1  
Cook County  
Contract No. 60J13  
Item No. 1, January 19, 2018 Letting  
Addendum B

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 2-7 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Priscilla Tobias,  
Director, Office of Program Development

A handwritten signature in black ink, appearing to read "Ted B. Walschleger" with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Anthony Quigley, Region 1, District 1; Tim Kell; Estimates

MS/ck

**STATUS OF UTILITIES (D-1)**

Effective: June 1, 2016

Utility companies and/or municipal owners located within the construction limits of this project have provided the following information in regard to their facilities and the proposed improvements. The tables below contain a description of specific conflicts to be resolved and/or facilities which will require some action on the part of the Department's contractor to proceed with work. Each table entry includes an identification of the action necessary and, if applicable, the estimated duration required for the resolution.

UTILITIES TO BE ADJUSTED

Conflicts noted below have been identified by following the suggested staging plan included in the contract. The company has been notified of all conflicts and will be required to obtain the necessary permits to complete their work; in some instances resolution will be a function of the construction staging. The responsible agency must relocate or complete new installations as noted in the action column; this work has been deemed necessary to be complete for the Department's contractor to then work in the stage under which the item has been listed.

Pre-Stage

| STAGE / LOCATION   | TYPE                | DESCRIPTION  | RESPONSIBLE AGENCY | ACTION  |
|--|---------------------|--|--------------------|---|
| Sta 95+95 (Lee), 16' LT to Sta. 99+88 (Lee), 16' LT to Sta. 18+50 (IL 68) 11' RT & Sta 19+30, 11' RT to 30' LT to Sta. | 4" Natural Gas Line | Crossed by new culvert at west end; under east leg crossed by new culvert; crossed by new storm sewers | Nicor              | All gas main adjustments to be completed by Nicor – <b>30 day duration</b>                                |
| Sta. 19+70, 42' RT to Sta. 20+22, 71' RT   | Fiber Optic         | Crossed by storm sewer and potential handhole adjustment   | Windstream         | All fiber optic adjustments to be completed by Windstream – <b>30 day duration</b>                        |
| Sta 99+22 (Lee), 22' RT to Sta 101+30, 8' RT, Sta 99+22 (Lee), 22' RT to Sta 20+37 (IL 68) 30' LT to Sta 23+50 37' LT  | Telephone           | Overhead and underground by new culvert, other storm sewer and relocation of utility poles             | AT&T               | All overhead and underground telephone line adjustments to be completed by AT&T – <b>180 day duration</b> |

Revised 1/10/18

|   |          |  |         |   |
|---|----------|--|---------|---|
| Sta. 99+22 (Lee)<br>22' RT to Sta<br>20+60, 39' LT to<br>Sta 23+50 39' LT                         | Electric | Utility poles will<br>need to be relocated<br>due to grade,<br>temporary widening<br>and new ROW             | ComEd   | All utility pole and<br>electric line<br>adjustments to be<br>completed by<br>ComEd – <b>40 day<br/>duration</b>                            |
| Sta 99+22 (Lee)<br>22'RT to 101 +30<br>8' Rt, 22<br>Stat20+60 (IL 68)<br>39'Lt to 23+50 39'<br>LT | Cable TV | On ComEd utility<br>poles that need to<br>be relocated due to<br>grade, temporary<br>widening and new<br>ROW | Comcast | All utility poles to be<br>adjusted by ComEd<br>and cable line<br>adjustments to be<br>completed by<br>Comcast – <b>20 day<br/>duration</b> |

Stage 1

|   |   |   |   |   |
|---|---|---|---|---|
| - | - | - | - | - |
|---|---|---|---|---|

Stage 2

| STAGE /<br>LOCATION | TYPE | DESCRIPTION | RESPONSIBLE<br>AGENCY | ACTION |
|---------------------|------|-------------|-----------------------|--------|
| -                   | -    | -           | -                     | -      |

No conflicts to be resolved (or if there are conflicts they are to be listed as noted above)

**Pre-Stage: 300 Days Total Installation**  
**Stage 1: 0 Days Total Installation**  
**Stage 2: 0 Days Total Installation**

The following contact information is what was used during the preparation of the plans as provided by the Agency/Company responsible for resolution of the conflict.

| Agency/Company Responsible to Resolve Conflict | Name of contact                            | Address  | Phone                           | e-mail address   |
|--|--|--|---------------------------------|--|
| AT&T   | Steve Larson & Bruce Robbins               | 1000 Commerce Drive<br>Oak Brook, IL 60523   | (630) 573-6471                  | br1831@att.com   |
| CECO   | Mark Tulach & Angela Harrell & Terri Bleck | ComEd – Public Relocation Department<br>One Lincoln Center Suite 600<br>Oakbrook Terrace, IL 60181 | (815) 477-5258 & (224) 422-7142 | angela.harrell@ComEd.com   |
| MWRDGC   | Hanif Munshi & Joseph Schuessler           | 100 East Erie Street<br>Chicago, IL 60611  | (312) 751-3184 & (312) 751-3226 | schuesslerj@mwrdd.org  |
| Nicor  | Bruce Koppang                              | 1844 Ferry Road<br>Naperville, IL 60563  | (630) 388-3046                  | bkoppang@aglresources.com  |
| Windstream                                     | Andres Bravo                               | 1815 S. Meyers Road,<br>Suite 900<br>Oakbrook Terrace, IL 60181                                    | (501) 748-4590                  | Barbara.Graves@windstream.com<br>&<br>Brandie.Mcgehee@windstream.com |

**UTILITIES TO BE WATCHED AND PROTECTED**

The areas of concern noted below have been identified by following the suggested staging plan included for the contract. The information provided is not a comprehensive list of all remaining utilities, but those which during coordination were identified as ones which might require the Department's contractor to take into consideration when making the determination of the means and methods that would be required to construct the proposed improvement. In some instances the contractor will be responsible to notify the owner in advance of the work to take place so necessary staffing on the owners part can be secured.

Pre-Stage

| <b>STAGE / LOCATION</b> | <b>TYPE</b> | <b>DESCRIPTION</b> | <b>OWNER</b> | <b>ACTION</b> |
|-------------------------|-------------|--------------------|--------------|---------------|
| -                       | -           | -                  | -            | -             |

Stage 1

| <b>STAGE / LOCATION</b> | <b>TYPE</b> | <b>DESCRIPTION</b> | <b>OWNER</b> | <b>ACTION</b> |
|-------------------------|-------------|--------------------|--------------|---------------|
| -                       | -           | -                  | -            | -             |

Stage 2

| STAGE / LOCATION   | TYPE           | DESCRIPTION   | OWNER  | ACTION                                 |
|--|----------------|---|--|--|
| Sta 18+50, 30' LT to Sta. 23+50, 30' LT & Sta 19+18, 0' LT to Sta. 19+18, 30' LT & Sta. 19+71, 39' LT to Sta 19+71, 105' LT & Sta 19+75, 30' RT                | Water Main     | WM under north side of IL 68 crossed by new culvert, including connection to north on Lee Road; also crossed by proposed storm sewer system   | Village of Northbrook (Work included in this Contract) | Watch and protect during construction. |
| Sta 20+57 , 34' LT to Sta. 20+90, 34' LT to Sta 18+81 30' LT & Sta. 95+95 (Lee) 15' LT to Sta 99+36, 13' LT to Sta 19+37 (IL 68), 15' RT to Sta. 19+33, 30' LT | Sanitary Sewer | Sanitary sewer crossing north leg of Lee Road crossed by new culvert, including through manholes; minor - along south leg of Lee, west side, grading above sanitary sewer with MH adjustments | Village of Northbrook (Work included in this Contract) | Watch and protect during construction. |
| Sta 19+81, 75' LT to Sta. 20+90, 34' LT  | Sanitary Sewer | Interceptor sewer serving north leg of Lee crossed by new culvert   | MWRDGC (Work included in this Contract)                | Watch and protect during construction. |

The following contact information is what was used during the preparation of the plans as provided by the owner of the facility.

| Agency/Company Responsible to Resolve Conflict | Name of contact                  | Address                                | Phone                           | e-mail address                |
|--|----------------------------------|--|---------------------------------|-------------------------------|
| Village of Northbrook                          | Kelly Hamill                     | 655 Huehl Northbrook, IL 60062         | (847) 272-4711                  | Kelly.hamill@northbrook.il.us |
| MWRDGC   | Hanif Munshi & Joseph Schuessler | 100 East Erie Street Chicago, IL 60611 | (312) 751-3184 & (312) 751-3226 | schuesslerj@mwrdd.org         |
| Village of Northbrook                          | Kelly Hamill                     | 655 Huehl Northbrook, IL 60062         | (847) 272-4711                  | Kelly.hamill@northbrook.il.us |

The above represents the best information available to the Department and is included for the convenience of the bidder. The days required for conflict resolution should be taken into account in the bid as this information has also been factored into the timeline identified for the project when setting the completion date. The applicable portions of the Standard Specifications for Road and Bridge Construction shall apply.

Estimated duration of time provided in the action column for the first conflicts identified will begin on the date of the executed contract regardless of the status of the utility relocations. The responsible agencies will be working toward resolving subsequent conflicts in conjunction with contractor activities in the number of days noted.

The estimated relocation dates must be part of the progress schedule submitted by the contractor. A utility kickoff meeting will be scheduled between the Department, the Department's contractor and the utility companies. The Department's contractor is responsible for contacting J.U.L.I.E. prior to any and all excavation work.