



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

December 20, 2017

SUBJECT: FAU 4304 (Rathje Road)  
Section 04-00045-01-FP (Peotone)  
Will County  
Contract No. 61E30  
Item 91  
January 19, 2018 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised the Schedule of Prices.**
- 2. Revised page 12 of the Special Provisions.**
- 3. Revised sheets 4 and 5 of the Plans.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bid.

Very truly yours,

Maureen M. Addis, P.E.  
Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

**Basis of payment**

This work will be paid for at the contract unit price EACH for LINE STOPS 12", which price shall include all materials, equipment and labor necessary to perform the work as herein specified.

**EXPLORATORY EXCAVATION**

This work shall be done in accordance with the Standard Specifications insofar as applicable included herein and including the following description.

The work of this pay item shall consist of providing service to complete an exploratory excavation at the depth necessary to establish elevation of existing public and private utilities in the field as directed by the Engineer.

After the evaluation and size of the utility has been determined, the trench (hole) shall be backfilled with trench backfill in a manner satisfactory to the Engineer. Excavated materials shall be disposed of in accordance with Article 202 of the Standard Specifications.

This work shall be paid for at the contract unit price per FOOT for EXPLORATORY EXCAVATION.

**DUST CONTROL**

When ordered by the engineer, the contractor shall use the following method to allay dust and prevent a nuisance within the limits of the construction site. Dust shall be controlled by the uniform application of sprinkled water and shall be applied only when directed by the engineer, in a manner meeting his approval. Calcium chloride shall not be used for this purpose. All equipment used for this work shall meet with the engineer's approval. This work shall consist of the exclusive control of dust resulting from construction operations and is not intended for use in the compaction of earth embankments, as specified under Article 205 of the Standard Specifications. No extra compensation shall be allowed to the contractor for this work.

**SOIL TESTING AND ANALYSIS**

If the Contractor will be using a Clean Construction or Demolition Debris (CCDD) facility, the Village requires that a facility is selected that will accept material per the data/test results provided on the enclosed LPC 663 form.