



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 3, 2024

SUBJECT: FAI Route 55 (I-55)
Project NHPP-5WZI(166)
Section (32-2)RS,BRR
Grundy County
Contract No. 66K67
Item No. 88, January 19, 2024 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 11 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

KEEPING ROADS OPEN TO TRAFFIC

(Effective December 1, 1999; Revised December 14, 2009)

All lanes shall be open to traffic during the legal holiday periods according to Article 107.09 of the Standard Specifications, during weekends defined as 3:00 p.m. Friday to 12:00 midnight Sunday, with the following two exceptions:

Lane closures for structure work on I-55 for Structure 032-0078 will be allowed overnight and on all calendar days when barrier wall is in place.

Lane closures for pavement patching will be allowed overnight except on weekends and legal holiday periods as defined above.

In order to minimize the length of lane closures during work operations, the following are required:

Lane closures shall be limited to one half mile ahead of the work operation. Priming is also limited to one half mile in advance of the paving machine.

During HMA paving when the HMA lift has hardened to the satisfaction of the Engineer, the Contractor shall advance the lane closure taper and signing in one-mile increments.

This work will not be paid for separately but shall be included in the cost of the applicable traffic control items.

UNEVEN LANES

(Effective July 24, 2000, Revised December 14, 2009)

Two "UNEVEN LANES" signs (W8-11(FO)) shall be installed at intervals not greater than 2 miles and on all entrance ramps when work creates a difference in elevation between lanes that will be open to traffic. These signs shall be removed or covered when the lanes are returned to the same elevation. These signs will not be paid for separately but shall be included in the cost of the applicable traffic control items.

PLASTIC DRUMS

(Effective August 15, 2005; Revised April 27, 2018)

Plastic drums according to Standard 701901 shall be used in lieu of cones, Type I and Type II barricades, and vertical barricades throughout lane closures.

Revised January 3, 2024