



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 2, 2024

SUBJECT: FAU 6915 (Adams Street)
Section 21-00151-00-SW (Macomb)
McDonough County
Contract No. 89829
Item 121
January 19, 2024 Letting
Addendum (A)

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised Special Provision Index**
- 2. Added page 12A to the Special Provisions**

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

INDEX OF SPECIAL PROVISIONS

ITEM	PAGE
1. DESCRIPTION OF WORK.....	1
2. COMPLETION DATE.....	1
3. UTILITIES	1
4. HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	2
5. PAVEMENT REMOVAL (SPECIAL)	2
6. SIDEWALK REMOVAL	2
7. SIDEWALK REMOVAL (SPECIAL).....	3
8. STORM SEWER REMOVAL.....	3
9. MANHOLES.....	3
10. INLETS	4
11. REMOVING MANHOLES; REMOVING INLETS.....	4
12. STORM SEWER CONNECTION	5
13. TEMPORARY SURFACE REPLACEMENT.....	5
14. PORTLAND CEMENT CONCRETE SIDEWALK	5
15. PORTLAND CEMENT CONCRETE SIDEWALK SMOOTHNESS	6
16. DETECTABLE WARNINGS (SPECIAL) (CAST IRON).....	6
17. COMBINATION CONCRETE CURB AND GUTTER TYPE B6.18 (ABUTTING EXISTING PAVEMENT).....	6
18. PORTLAND CEMENT CONCRETE INLAY, 5".....	7
19. PORTLAND CEMENT CONCRETE PAVEMENT, FURNISHED.....	7
20. PAVEMENT FABRIC (SPECIAL).....	8
21. GROUT SLURRY (SPECIAL)	8
22. PIPE HANDRAIL.....	8
23. CONCRETE STEPS	9
24. AGGREGATE QUALITY	9
25. TRAFFIC CONTROL AND PROTECTION, (SPECIAL).....	9
26. SEEDING, COMPLETE	10
27. INCLUDED ITEMS	11
28. RELOCATE EXISTING SIGNS	11
29. RETAINING WALL REMOVAL	12
30. PAVEMENT PATCHING (SPECIAL).....	12
PCC QMP ELECTRONIC REPORT SUBMITTALS.....	12A
PCC QUTOMATIC BATCHING EQUIPMENT	12A
LR 107-4.....	13
LR 702.....	14
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING.....	15
STORM WATER POLLUTION PREVENTION PLAN.....	17

PCC QMP ELECTRONIC REPORT SUBMITTALS

Effective: January 13, 2022

The Contractor's QC personnel shall be responsible for electronically submitting the following reports to the Department: PRO and IND data for BMPR MI654 "Air, Slump, & Quantity"; PRO data for BMPR MI655 "PCC Strength"; and PRO data for BMPR MI504 "Field/Lab Gradation". The format for the electronic submittals will be the "QMP" reporting program which will be provided by the Department. Microsoft Office 2007 or newer is required for this program which must be provided by the Contractor.

PCC AUTOMATIC BATCHING EQUIPMENT

Effective: April 23, 2010 Revised: August 1, 2023

Portland cement concrete provided shall be produced from batch plants that conform to the requirements of Article 1103.03 (a) and (b) of the Standard Specifications for Road and Bridge Construction. Semi-automatic batching will not be allowed.

Plants shall have computerized batching interfaced with a printer. IDOT Producer Number, IDOT Concrete Material Code, batch weights, aggregate mixtures, water added, amount of each admixture or additive, and percent variance from design shall be printed for each batch. The ticket shall state the actual water-cement ratio as batched, and the amount of water that can be added to the batch without exceeding the maximum water-cement ratio. Truck delivery tickets will still be required as per Article 1020.11 (a)(7) of the Standard Specifications.