



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

January 17, 2006

SUBJECT: FAI Route 80/94  
Project ACNHI-080-5(065)160  
Section (0203.1&0304)R-6  
Cook County  
Contract No. 62105  
Item No. 1P, January 20, 2006 Letting  
Addendum C

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 40 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Michael L. Hine  
Engineer of Design  
and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; N. R. Stoner; Roger Driskell;  
R. E. Anderson; Estimates; Design & Environment File

TK/cab

Add the following to Article 311.03:

“(h) Vibratory Roller .....1101.01 (g)”

Revise Article 311.05(c) to read:

“(c) Subbase Granular Material, Type B. The manner of placing and compacting the material shall be approved by the Engineer prior to starting the work.

The Granular subbase shall be constructed in layers not more than 2 ft. thick when compacted. Each layer shall be compacted with a vibratory roller to the satisfaction of the Engineer.

After completion of the granular subbase, the granular subbase cap shall be placed. Each layer shall be compacted with a vibratory roller to the satisfaction of the Engineer.

If the moisture content of the material is insufficient to obtain satisfactory compaction, sufficient water shall be added, at the Contractors expense, so that satisfactory compaction can be obtained.”

Revise that first sentence of the first paragraph of Article 311.08 (b) to read:

“Aggregate used in the granular subbase and granular subbase cap will be measured for payment in square meters (square yards).”

Stabilized Sub Base: This work shall be performed according to the special provision, “Superpave Bituminous Concrete Mixtures”. The mixture used shall be the Superpave IL-19.0, N50, 3.0% voids.

Pavement and Shoulders: Add the following to Articles 420.03, 421.03, and 483.03:

“The Contractor shall submit to the Engineer, for approval before paving, the proposed internal type vibrator spacing for the paver. The Contractor shall also provide the proposed vibrator operating frequencies for a paving speed greater than or equal to 3 ft./min. and a paving speed less than 3 ft/min.”

Add the following to Article 421.05:

“When the surface temperature, as measured on the surface with a device as approved by the Engineer, of the Stabilized Sub-base is 115°F or greater the Contractor shall spray the Stabilized Sub-base with a water mist with equipment that meets the approval of the Engineer. The Stabilized Sub-base shall be cooled below 115°F prior to paving on top. The water spray shall not produce excessive water runoff or leave puddles on the Stabilized Sub-base at the time of paving. All cooling shall be completed a minimum of 10 minutes prior to paving. The surface temperature shall be monitored during the paving operation to determine if the Stabilized Sub-base requires re-spraying.

The water used shall meet the requirements of Section 1002.”

Portland Cement Concrete:” Revise Article 1020.02 (d) to read:

“(d) Coarse Aggregate (Note 1) .....1004.01 – 1004.02”

Revised 1/17/2006