

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	231	10
STA.		TO STA.		
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT	
*(0203.1 & 0304) R-6		CONTRACT # 62105		

CODE NO.	PAY ITEM	UNIT	URBAN 90% FED. 10% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY J000-2A	SIGNING Y002-1C	ELECTRICAL WORK Y030-1E
MX030505	STORM SEWERS TO BE GROUTED	CU M	107	107		
X0301229	ACCIDENT INVESTIGATION SITE	CAL MO	12	12		
* MX032160	CONDUIT ENCASED, REINFORCED CONCRETE, 100 MM DIA. PVC, 2 WIDE X 1 HIGH	METER	202			202
MX032178	TEMPORARY INFORMATION SIGNING	SQ M	6	6		
X0323879	SERVICE PATROL	CAL DA	668	668		
X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	5	5		
X0324045	SEDIMENT CONTROL STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	3	3		
X0324698	APPLY DUST SUPPRESSION AGENTS	UNIT	243	243		
MX033183	SOIL STABILIZERS	KG	216,000	216,000		
MX033234	SLOTTED DRAIN REMOVAL	METER	346	346		
MX033290	SEDIMENT CONTROL, SILT FENCE	METER	3,210	3,210		
MX033291	SEDIMENT CONTROL, SILT FENCE MAINTENANCE	METER	3,210	3,210		
MX033292	SEDIMENT CONTROL STABILIZED CONSTRUCTION ENTRANCE	SQM	408	408		
MX033303	SEDIMENT CONTROL STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQM	816	816		
X0504200	CONCRETE HEADWALL	EACH	4	4		
X0976500	END SECTIONS TO BE REMOVED	EACH	2	2		
X6020166	DRAINAGE STRUCTURES, TYPE 1 SPECIAL WITH TWO TYPE 20 FRAME AND GRATES	EACH	6	6		
X6020167	DRAINAGE STRUCTURES, TYPE 2 SPECIAL WITH TWO TYPE 22 FRAME AND GRATES	EACH	2	2		
MX602340	CATCH BASINS, 1.2M BY 1.5M, TYPE 22 FRAME AND GRATE	EACH	1	1		
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	12	12		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1		
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	288	288		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	8	8		
MX704200	REMOVE TEMPORARY CONCRETE BARRIER	METER	4,884	4,884		
MZ001050	AGGREGATE SUBGRADE 300MM	SO M	1,378	1,378		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1		
<input type="checkbox"/> Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	5	5		
<input type="checkbox"/> Z0030270	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	4	4		
<input type="checkbox"/> Z0076600	TRAINEES	HOUR	500	500		

- SFTY-3N
- Y080
- \* SPECIALTY ITEMS

SQ-5

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION F.A.I. ROUTE 80/94 (INTERSTATE 80/294)
NAME	DATE	
		SUMMARY OF QUANTITIES  DATE: JULY 18, 2005 DRAWN BY: AAS CHECKED BY: RCH 