F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	*	COOK	631	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* (2425 & 2626) R-2 CONTRACT NO. 62111

SUMMARY OF QUANTITIES

	CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY		I-80 ** J000-2A	RAILROAD, BURNHAM, 175TH ST., BERNICE ** I000-2A	BRIDGE ** 016-2791 X271-2A	BRIDGE ** 016-2792 X281-2A	RETAINING WALLS ** Y007	SURVEILLANCE ** Y032-1F	LANSING **** I000-2A		SIGNING ** Y002-1C				
	M5510060	STORM SEWER REMOVAL 600MM	METER	60		60												
	M5510095	STORM SEWER REMOVAL 1200MM	METER	261.5		54.5	207											
	M5910100	GEOCOMPOSITE WALL DRAIN	SQ M	547						547								
	M6010610	PIPE UNDERDRAINS 150MM	METER	4399		4399												
	M6011105	PIPE UNDERDRAINS FOR STRUCTURES 150MM	METER	103						103								
	M6020105	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	16		3	8					5						
	M6020140	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 8 GRATE	EACH	6			6											
	M6020185	CATCH BASINS, TYPE A, 1.2M DIAMETER, TYPE 24 FRAME AND GRATE	EACH	12			12											
	M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3			1					2						
	M6021810	MANHOLES, TYPE A, 1.8M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2											
	M6022010	MANHOLES, TYPE A, 2.1M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2											
	M6060070	CONCRETE CURB, TYPE B	METER	14			14											
	M6060500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.30	METER	665			401					264						
	M6060700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-15.60	METER	756			756											
	M6063630	CONCRETE MEDIAN SURFACE, 150MM (SPECIAL)	SQ M	1132		1132												
	M6320030	GUARDRAIL REMOVAL	METER	73		73												
	M6370155	CONCRETE BARRIER, SINGLE FACE, 815 MM HEIGHT	METER	742		742												
	M6370175	CONCRETE BARRIER, SINGLE FACE, 1065 MM HEIGHT	METER	58		58												
	M6370255	CONCRETE BARRIER, DOUBLE FACE, 815MM HEIGHT	METER	435		435												
	M6370275	CONCRETE BARRIER, DOUBLE FACE, 1065 MM HEIGHT	METER	2101		2101												
	M6370805	CONCRETE BARRIER TRANSITION	METER	39		39												
△	MX03405	CONCRETE BARRIER BASE	METER	3850		3850												
⊙⊙	M6380600	MODULAR GLARE SCREEN SYSTEM	METER	364.7		364.7												
	M6420015	SHOULDER RUMBLE STRIP	METER	13881		13881												
	M7030210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	13			13											
	M7030220	TEMPORARY PAVEMENT MARKING - LINE 100MM	METER	2401		2401												
	M7030240	TEMPORARY PAVEMENT MARKING - LINE 150MM	METER	11426		10678	748											
	M7030260	TEMPORARY PAVEMENT MARKING - LINE 300MM	METER	65		65												
	M7030280	TEMPORARY PAVEMENT MARKING - LINE 600MM	METER	18		18												
	M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	12915		12915												
	M7030530	PAVEMENT MARKING TAPE, TYPE III 125MM	METER	1092		1092												
	M7030550	PAVEMENT MARKING TAPE, TYPE III 200MM	METER	1280		1280												
	M7030560	PAVEMENT MARKING TAPE, TYPE III 300MM	METER	342		342												
	M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	1886		1886												
	M7040100	TEMPORARY CONCRETE BARRIER	METER	1277		903	374											
*	M7200100	SIGN PANEL - TYPE 1	SQ M	30										30				
*	M7200200	SIGN PANEL - TYPE 2	SQ M	13.7										13.7				
*	M7200300	SIGN PANEL - TYPE 3	SQ M	155.2										155.2				

*SPECIALTY ITEMS

**90% FEDERAL
10% STATE

***50% STATE
50% VILLAGE OF LANSING

****100% VILLAGE OF LANSING

*****100% CITY OF CHICAGO HEIGHTS

##90% FEDERAL
5% STATE
5% VILLAGE OF LANSING

⊙⊙ SFTY-2A 90% FED./10% STATE

△ Rev. 12-6-05

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.I. ROUTE 80/94 (KINGERY EXPRESSWAY)
EB & WB INSIDE LANES (MAINLINE) CONSTRUCTION
COOK COUNTY

SUMMARY OF QUANTITIES IV

SCALE: NONE
DATE: 9/13/05

DRAWN BY: SNM
CHECKED BY: KC

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
CHICAGO, ILLINOIS

..\S0178O2A.DGN, ..\S0178O2A.DGN, ..\A8990O2A.DGN
9-14-2005, SubZ38, T:\DOCUMENT\83750\CIVIL\DGN\S0170042A.DGN
STANKRJ