

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	28-50-M	JO DAVIESS	27	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	CONSTRUCTION TYPE CODE Y022 TOTAL QUANTITY
20101700	SUPPLEMENTAL WATERING	UNIT	93
20200100	EARTH EXCAVATION	CU YD	18
20200500	EARTH EXCAVATION (WIDENING)	CU YD	384
20400800	FURNISHED EXCAVATION	CU YD	43
25200100	SODDING	SQ YD	2069
35102400	AGGREGATE BASE COURSE, TYPE B 12"	SQ YD	1532
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.3
40500300	BITUMINOUS MIXTURE COMPLETE	TON	1091
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	461
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2710
44000600	SIDEWALK REMOVAL	SQ FT	1108
60600605	CONCRETE CURB, TYPE B	FOOT	245
60603300	GUTTER OUTLET	EACH	1
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24	FOOT	345
67100100	MOBILIZATION	L SUM	1
* 72000100	SIGN PANEL - TYPE 1	SQ FT	4
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	24
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	6
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7071
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	13
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	28
A2006714	TREE, QUERCUS MACROCARPA (BUR OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	3
A2007114	TREE, QUERCUS RUBRA (RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	3
X4200400	PORTLAND CEMENT CONCRETE PAVEMENT 8", (SPECIAL) WITH INTEGRAL CURB	SQ YD	11
X0300019	REMOVE AND REINSTALL PARKING BLOCKS	EACH	2
X0301430	PRECAST CONCRETE PARKING BLOCK	EACH	1
X0321309	CONCRETE PAD	SQ YD	19
X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	34
X4420132	CLASS D PATCHES (SPECIAL)	SQ YD	29
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1
XX004144	DRINKING FOUNTAIN	EACH	1
XX005896	CONCRETE PAD REMOVAL	SQ FT	241
Z0049400	REFUSE CONTAINER AND PAD	EACH	2
* X0325136	DRILLED WATER WELL COMPLETE	L SUM	1
X0325137	REMOVE AND RELOCATE PICNIC TABLE AND SHELTER	L SUM	1
X0325138	REMOVE AND REPLACE PRIVACY FENCE	L SUM	1
X0325139	ROOF REPAIR	L SUM	1
X0325140	WOODEN GUARDRAIL REPAIR	L SUM	1

* SPECIALTY ITEM

PLOT DATE = Fri Sep 02 11:04:44 2005
 PLOT SCALE = 1:8000
 PLOT SCALE = 1:8000
 REFERENCE = #REF#

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

REVISIONS	
NAME	DATE

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY SAM
 CHECKED BY RJA