

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	28-SO-M	JO DAVIESS	27	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

20101700 SUPPLEMENTAL WATERING

LOCATION	UNITS	REMARKS
10+00.00 TO 15+00.00	18.0	ENTRANCE ROAD
15+00.00 TO 18+39.54	5.5	ENTRANCE ROAD
20+00.00 TO 22+00.00	3.2	GORE AREA
22+00.00 TO 24+00.00	2.4	CIRCULATORY ROADWAY
24+00.00 TO 27+50.00	33.3	PARKING AREA
27+50.00 TO 34+00.00	21.2	CIRCULATORY ROADWAY
34+00.00 TO 36+00.00	4.1	GORE AREA
REPAIR / REPLACE SIDEWALK PERIMETER	1.9	
EXISTING SIDEWALK PERIMETER	2.6	
30+40.00 RT	0.8	DUMPSTER PAD
TOTAL	93	

25200100 SODDING

LOCATION	SQ YD	REMARKS
10+00.00 TO 15+00.00	400.0	ENTRANCE ROAD
15+00.00 TO 18+39.54	121.5	ENTRANCE ROAD
20+00.00 TO 22+00.00	70.8	GORE AREA
22+00.00 TO 24+00.00	54.2	CIRCULATORY ROADWAY
24+00.00 TO 27+50.00	740.3	PARKING AREA
27+50.00 TO 34+00.00	470.8	CIRCULATORY ROADWAY
34+00.00 TO 36+00.00	91.7	GORE AREA
REPAIR / REPLACE SIDEWALK PERIMETER	42.0	
EXISTING SIDEWALK PERIMETER	57.6	
30+40.00 RT	20.0	DUMPSTER PAD
TOTAL	2069	

35102400 AGGREGATE BASE COURSE, TYPE B, 12"

LOCATION	SQ YD	REMARKS
24+09.00 TO 27+50.00 RT	557.1	AT PARKING RIGHT SIDE
25+50.00 TO 27+68.00 LT	624.9	AT PARKING LEFT SIDE
29+40.00 TO 35+08.00 LT	339.8	AT WIDENING LEFT SIDE
30+31.00 TO 30+45.00 RT	10.7	AT DUMPSTER PAD
TOTAL	1532	

40500100 BITUMINOUS MATERIALS (PRIME COAT)

LOCATION	TON	REMARKS
10+00.00 TO 15+00.00	0.30	ENTRANCE ROAD
15+00.00 TO 22+00.00	0.28	ENTRANCE ROAD
22+00.00 TO 24+00.00	0.05	GORE
24+00.00 TO 27+50.00	0.35	PARKING AREA
27+50.00 TO 34+00.00	0.26	CIRCULATORY ROADWAY
34+00.00 TO 36+00.00	0.06	RETURN GORE AREA
TOTAL	1.3	

40500300 BITUMINOUS MIX COMPLETE

LOCATION	TON	REMARKS
10+00.00 TO 15+00.00	249.6	ENTRANCE ROAD
15+00.00 TO 22+00.00	238.2	ENTRANCE ROAD
22+00.00 TO 24+00.00	42.0	GORE
24+00.00 TO 27+50.00	292.4	PARKING AREA
27+50.00 TO 34+00.00	222.2	CIRCULATORY ROADWAY
34+00.00 TO 36+00.00	46.6	RETURN GORE AREA
TOTAL	1091	

40600980 BITUMINOUS SURFACE REMOVAL BUTT JOINT

LOCATION	SQ YD	REMARKS
10+00.00 TO 10+30.00 LT TO RT	221.1	OVERLOOK ENTRANCE
15+46.00 TO 24+09.00 RT	191.8	LOWER PARKING AREA
23+33.00 TO 25+50.00 LT	48.2	LOWER PARKING AREA
TOTAL	461	

42400200 PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH

LOCATION	SQ FT	REMARKS
25+50.00 TO 27+50.00 LT	1500.0	ALONG PARKING AREA
26+10.00 TO 26+40.00 LT	339.0	AT SIDEWALK REPLACEMENT AREA
26+90.00 TO 27+10.00 LT	90.0	AT SIDEWALK EXTENSION AREA
24+43.00 TO 24+50.00 LT	50.6	AT SIDEWALK REPAIR AREAS
24+75.00 TO 24+82.00 LT	49.8	AT SIDEWALK REPAIR AREAS
24+95.00 TO 25+25.00 LT	276.1	AT SIDEWALK REPAIR AREAS
25+10.00 TO 25+22.00 LT	72.0	AT SIDEWALK REPAIR AREAS
25+30.00 TO 25+39.00 LT	51.6	AT SIDEWALK REPAIR AREAS
25+40.00 TO 25+50.00 LT	48.5	AT SIDEWALK REPAIR AREAS
25+65.00 TO 25+75.00 LT	54.0	AT SIDEWALK REPAIR AREAS
25+76.00 TO 25+86.00 LT	61.3	AT SIDEWALK REPAIR AREAS
26+33.00 TO 26+50.00 LT	117.3	AT SIDEWALK REPAIR AREAS
TOTAL	2710	

EARTHWORK SCHEDULE

LOCATION	20200100 EARTH EXCAVATION (CUT)	20200500 EARTH EXCAVATION (WIDENING)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)
FRGM TO					
ENTRANCE ROAD					
10+00.00 TO 15+00.00	0.0	0.0	0.0	6.5	-6.5
15+00.00 TO 18+39.54	0.0	0.0	0.0	3.0	-3.0
20+00.00 TO 22+00.00	0.0	0.0	0.0	1.9	-1.9
22+00.00 TO 24+00.00	0.0	0.0	0.0	1.6	-1.6
PARKING AREA					
24+00.00 TO 27+50.00	15.7	149.5	123.9	317.2	-193.3
CIRCULATORY ROADWAY					
27+50.00 TO 34+00.00	2.1	180.1	136.7	12.2	124.4
34+00.00 TO 36+00.00	0	54.5	40.9	1.9	39.1
TOTALS	18	384	301	344	43
	20200100 EARTH EXCAVATION 18 CU YD	20200500 EARTH EX (WIDENING) 384 CU YD			20400800 FURNISHED EXCAVATION 43 CU YD

44000600 SIDEWALK REMOVAL

LOCATION	SQ FT	REMARKS
25+50.00 TO 25+60.00 LT	101.7	ALONG PARKING AREA
26+10.00 TO 26+40.00 LT	225.0	AT SIDEWALK REPLACEMENT AREA
24+43.00 TO 24+50.00 LT	50.6	AT SIDEWALK REPAIR AREAS
24+75.00 TO 24+82.00 LT	49.8	AT SIDEWALK REPAIR AREAS
24+95.00 TO 25+25.00 LT	276.1	AT SIDEWALK REPAIR AREAS
25+10.00 TO 25+22.00 LT	72.0	AT SIDEWALK REPAIR AREAS
25+30.00 TO 25+39.00 LT	51.6	AT SIDEWALK REPAIR AREAS
25+40.00 TO 25+50.00 LT	48.5	AT SIDEWALK REPAIR AREAS
25+65.00 TO 25+75.00 LT	54.0	AT SIDEWALK REPAIR AREAS
25+76.00 TO 25+86.00 LT	61.3	AT SIDEWALK REPAIR AREAS
26+33.00 TO 26+50.00 LT	117.3	AT SIDEWALK REPAIR AREAS
TOTAL	1108	

60600605 CONCRETE CURB, TYPE B

LOCATION	FEET	REMARKS
25+50.00 TO 27+70.00 LT	245.0	ALONG PARKING AREA
TOTAL	245	

60603300 GUTTER OUTLET

LOCATION	CACH	REMARKS
27+50.00 TO 27+80.00 RT	1	AT BUS PARKING AREA
TOTAL	1	

60607400 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.24

LOCATION	FEET	REMARKS
24+09.00 TO 27+54.00 RT	345.0	AT BUS PARKING AREA
TOTAL	345	

67100100 MOBILIZATION

LOCATION	L SUM	REMARKS
ENTIRE JOBSITE	1	
TOTAL	1	

72000100 SIGN PANEL - TYPE 1

LOCATION	SQ FT	REMARKS
26+00.00 TO 26+15.00 TO	33' LT	PER D2 CAD STD 44.2
	33' LT	PER D2 CAD STD 44.2
TOTAL	4	

PLOT DATE = 8/12/05
FILE NAME = 8/12/05
PLOT SCALE = 1"=40'
REFERENCE = REF

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: VERT. _____
HORIZ. _____

DATE _____

DRAWN BY: SAM
CHECKED BY: RJA

REVISIONS	
NAME	DATE