

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	28-SO-M	JO DAVIESS	27	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

72800100 TELESCOPING STEEL SIGN SUPPORT

LOCATION	FEET	REMARKS
26+06.00 TO 26+23.00 TO	33' LT	PER D2 CAD STD 44.2
	33' LT	PER D2 CAD STD 44.2
TOTAL		24

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

LOCATION	SQ FT	REMARKS
26+00.00 TO 26+15.00 TO	15' LT	HANDICAPPED PARKING SYMBOL
	15' LT	HANDICAPPED PARKING SYMBOL
TOTAL		6

78000200 THERMOPLASTIC PAVEMENT MARKING, LINE 4"

LOCATION	FEET	REMARKS
10+00.00 TO 11+00.00	RT	72.5 WHITE EDGE LINE
10+00.00 TO 11+00.00	CL	100.0 YELLOW CENTERLINE
10+00.00 TO 11+00.00	CL	100.0 YELLOW CENTERLINE
10+00.00 TO 11+00.00	LT	131.7 WHITE EDGE LINE
11+00.00 TO 15+00.00	RT	377.0 WHITE EDGE LINE
11+00.00 TO 15+00.00	CL	400.0 YELLOW CENTERLINE
11+00.00 TO 15+00.00	CL	400.0 YELLOW CENTERLINE
11+00.00 TO 15+00.00	LT	400.7 WHITE EDGE LINE
15+00.00 TO 18+39.54	RT	339.5 WHITE EDGE LINE
15+00.00 TO 18+39.54	CL	339.5 YELLOW CENTERLINE
15+00.00 TO 18+39.54	CL	339.5 YELLOW CENTERLINE
15+00.00 TO 18+39.54	LT	339.5 WHITE EDGE LINE
20+00.00 TO 22+00.00	RT	197.6 WHITE EDGE LINE
20+00.00 TO 22+00.00	RT	197.6 YELLOW EDGE LINE
22+00.00 TO 30+07.40	RT	888.0 WHITE EDGE LINE
22+00.00 TO 24+38.50	RL	247.5 YELLOW EDGE LINE
24+48.60 TO 26+01.70	LT	346.0 YELLOW PARKING LINE
26+12.00 TO 26+18.50	LT	105.0 YELLOW PARKING LINE
26+28.80 TO 27+37.50	LT	238.0 YELLOW PARKING LINE
27+39.00 TO 34+00.00	LT	684.0 YELLOW EDGE LINE
30+09.40 TO 30+33.20	RT	52.6 YELLOW PARKING LINE
30+33.20 TO 34+00.00	RT	375.1 WHITE EDGE LINE
34+00.00 TO 36+00.00	RT	200.0 WHITE EDGE LINE
34+00.00 TO 36+00.00	RT	200.0 YELLOW EDGE LINE
TOTAL		7071

78000600 THERMOPLASTIC PAVEMENT MARKING, LINE 12"

LOCATION	FEET	REMARKS
20+46.30 TO 21+08.80	RT	12.9 YELLOW GORE STRIPING
TOTAL		13

78000650 THERMOPLASTIC PAVEMENT MARKING, LINE 24"

LOCATION	FEET	REMARKS
10+00.00 TO 10+02.00	RT	28.0 WHITE STOP LINE
TOTAL		28

LR420129 PORTLAND CEMENT CONCRETE PAVEMENT 8" (SPECIAL) WITH INTEGRAL CURB

LOCATION	SQ FT	REMARKS
30+40.00	RT	10.7 AT DUMPSTER AREA
TOTAL		11

X0300019 REMOVE AND REINSTALL PARKING BLOCKS

LOCATION	EACH	REMARKS
30+20.00	28' RT	1 AT REAR PARKING AREA
30+29.00	28' RT	1 AT REAR PARKING AREA
TOTAL		2

X0301430 PRECAST CONCRETE PARKING BLOCK

LOCATION	EACH	REMARKS
30+12.00	32' RT	1 AT REAR PARKING AREA
TOTAL		1

X0321309 CONCRETE PAD

LOCATION	SQ YD	REMARKS
27+57.00	24' LT	18.8 AT RELOCATED SHELTER
TOTAL		19

WOODEN GUARDRAIL REPAIR

LOCATION	L SUM	REMARKS
10+45.00 TO 11+20.00	LT	1 AT REST AREA ENTRANCE
TOTAL		1

X4400220 CURB REMOVAL AND REPLACEMENT

LOCATION	FEET	REMARKS
24+09.00 TO 24+12.00	LT	3.0 AT PARKING AREA
24+43.00 TO 24+73.00	LT	30.0 AT PARKING AREA
24+81.00 TO 24+82.00	LT	1.0 AT PARKING AREA
TOTAL		34

X4420132 CLASS D PATCHES (SPECIAL)

LOCATION	SQ YD	REMARKS
26+00.00 TO 26+05.00	RT	4.5 CIRCULATORY ROADWAY
29+40.00 TO 29+53.00	RT	18.8 CIRCULATORY ROADWAY
30+69.00 TO 30+93.00	RT	5.3 CIRCULATORY ROADWAY
TOTAL		29

XX004144 DRINKING FOUNTAIN

LOCATION	EACH	REMARKS
26+04.00	34' LT	1 AT PARKING AREA
TOTAL		1

Z0049400 REFUSE CONTAINER AND PAD

LOCATION	EACH	REMARKS
26+66.00	34' LT	1 AT PARKING AREA
27+45.00	35' LT	1 AT PARKING AREA
TOTAL		2

XX005896 CONCRETE PAD REMOVAL

LOCATION	SQ FT	REMARKS
25+70.00	36' LT	171.6 AT PARKING AREA
26+20.00	34' LT	6.3 AT PARKING AREA
26+20.00	34' LT	63.0 AT PARKING AREA
TOTAL		241

#2001342 DRILLED WATER WELL, COMPLETE

LOCATION	EACH	REMARKS
24+35.00	70' LT	1 AT PARKING AREA
TOTAL		1

X7013015 TRAFFIC CONTROL FOR ROAD CLOSURE

LOCATION	L SUM	REMARKS
ENTIRE JOBSITE		1
TOTAL		1

#2001343 REMOVE AND RELOCATE PICNIC TABLE AND SHELTER

LOCATION	L SUM	REMARKS
25+70.00 TO 27+50.00	24' LT	1 AT PARKING AREA
TOTAL		1

#2001345 ROOF REPAIR

LOCATION	L SUM	REMARKS
25+10.00	42' LT	1 ON TOWER
TOTAL		1

#2001344 REMOVE AND REPLACE PRIVACY FENCE

LOCATION	L SUM	REMARKS
26+25.00 TO 26+55.00	LT	1 AT REST ROOMS
TOTAL		1

A2006714 TREE, QUERCUS MACROCARPA (BUR OAK) 1-3/4" CALIPER, B AND B

LOCATION	EACH	REMARKS
ENTIRE JOBSITE		3.0 LOCATION BY IDOT
TOTAL		3

A2007114 TREE, QUERCUS RUBRA (RED OAK) 1-3/4" CALIPER, BALLED AND BURLAPPED

LOCATION	EACH	REMARKS
ENTIRE JOBSITE		3.0 LOCATION BY IDOT
TOTAL		3

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

REVISIONS	
NAME	DATE

SCALE: VERT. HORIZ. DATE

DRAWN BY SAM CHECKED BY RJA