

SUMMARY OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO
599	ROCK ISLAND	90	5
EXISTING CONDITIONS:			
* 20% F-1, SBR-2M			
			CONTRACT 64641

←80% FED — 20% STATE →

CODE NUMBER	ITEM	UNITS	TOTAL	I000-2A	X028-2A SN 081-1009	Y060 VILLAGE OF ANDALUSIA 100% Village	SN 081-1008 X028-2A 80 % FED 20 % STATE	SN 081-0076 SFTY-2A 80 % FED 20 % STATE
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	1	1				
54213870	STEEL END SECTIONS 15"	EACH	9	9				
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	112	112				
542D1060	PIPE CULVERTS, CLASS D, TYPE 2 15"	FOOT	44	44				
542D1111	PIPE CULVERTS, CLASS D, TYPE 2 66"	FOOT	120	120				
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	742	742				
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	116	116				
* 56103100	DUCTILE IRON WATER MAIN 8"	FOOT	375			375		
* 56105000	WATER VALVES 8"	EACH	2			2		
* 56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	1			1		
* 56400700	FIRE HYDRANTS (SPECIAL)	EACH	1	1				
60100915	PIPE DRAINS 6"	FOOT	50	50				
60100925	PIPE DRAINS 8"	FOOT	50	50				
60100935	PIPE DRAINS 10"	FOOT	50	50				
60100945	PIPE DRAINS 12"	FOOT	50	50				
60100955	PIPE DRAINS 15"	FOOT	54	54				
60200805	CATCH BASINS, TYPE A, 4' - DIAMETER, TYPE 8 GRATE	EACH	2	2				
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	1	1				
60209510	CATCH BASINS, TYPE C, WITH SPECIAL FRAME AND GRATE	EACH	6	6				
60249500	VALVE BOXES 8"	EACH	2			2		
60405900	GRATES AND COVERS, TYPE 2B	EACH	1	1				
60500060	REMOVING INLETS	EACH	1	1				
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2.2	2.2				
60602800	CONCRETE GUTTER, TYPE B	FOOT	362	362				
60900515	CONCRETE THRUST BLOCKS	EACH	5			5		
61100605	MISCELLANEOUS CONCRETE	CU YD	1	1				
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	1	1				
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	350				350	
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4				4	
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	4				4	
63200310	GUARDRAIL REMOVAL	FOOT	790	423			367	
63500105	DELINEATORS	EACH	7	3			4	
66300105	CALCIUM CHLORIDE APPLIED	TON	14	14				
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	15	15				
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	4	2			2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9				
67100100	MOBILIZATION	L SUM	1	0.67			0.33	
70100405	TRAFFIC CONTROL AND PROTECTION STD 701321	EACH	1				1	
70100450	TRAFFIC CONTROL AND PROTECTION STD. 701201	L SUM	1				1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1				
70101700	TRAFFIC CONTROL AND PROTECTION	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DAY	270	270				
70106500	TEMPORARY BRIDGE SIGNALS	EACH	1				1	
* 70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	446	446				
+ 70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	6,844	6,844				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	960	650			310	

* SPECIALTY ITEM
+ SFTY-3N ITEM