

PAVEMENT SCHEDULE

FAP NO:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
599	42MFT-BR & 42MFT-T	ROCK ISLAND	90	16
STA.	TO STA.			

EXISTING CONDITIONS:
CONTRACT 64641

LOCATION	LENGTH	BIT SUR RM (VAR DP) (SQ YD)	PAVEMENT REMOVAL (SQ YD)	SUB GRAN MAT A 12 (SQ YD)	SUB GRAN MAT A 4 (SQ YD)	BIT C PVT FD SUP 12 (SQ YD)	LEV BIND MM SUPER N50 (TON)	LEV BIND HM SUPER N50 (TON)	BC BC SUP IL-19.0 N50 (TON)	BC SC SUPER "D", N50 (TON)	BC SC SUPER "C", N50 (TON)	BIT SHLD SUPER 6 (SQ YD)	AGG SHLDS B (TON)	INCD BIT SUR SUPER (TON)	AGG BASE CSE B (TON)
SECTION 42MFT-BR															
404+30.00 405+00.00	70.0	200.7					10.3	1.1		22.7					
411+00.00 411+46.00	46.0	132.4			34.5					14.9					
405+00.00 407+70.00	270.0								112.2	87.7					
404+30.00 407+70.00	340.0				179.7										
407+70.00 411+00.00	330.0		936.3	1,205.7		953.3									
404+30.00 411+46.00	716.0									18.1		161.1	102.6		
405+50.00 LT ENTRANCE														10.4	42.3
406+85.00 LT ENTRANCE														17.9	72.7
406+00.00 RT ENTRANCE														12.4	50.4
406+91.00 RT ENTRANCE														5.5	22.2
410+37.00 LT ENTRANCE														55.4	224.5
(INCLUDES PARKING LOT)															
409+35.00 & 410+37.00 RT ENTRANCE														28.2	114.4
SUBTOTAL SECTION 42MFT-BR		333.1	936.3	1,205.7	214.2	953.3	10.3	1.1	112.2	125.3	18.1	161.1	102.6	129.8	526.5
ROUNDED SUBTOTAL SECTION 42MFT-BR		334	937	1,206	215	954	11	2	113	126	19	162	103	130	527
326+50.00 329+50.00	300.0	645.0													
335+55.00 336+10.00	55.0	79.4													
330+00.00 335+00.00	500.0		1,455.8	1,611.1		1,444.4									
327+77.00 331+02.50	325.5				191.2										
327+00.00 328+00.00	100.0						4.5	0.4							
335+60.00 336+00.00	40.0						3.5	0.4							
328+00.00 330+00.00	200.0								70.7						
335+00.00 335+60.00	60.0								39.0						
326+50.00 330+00.00	350.0									113.6					
335+00.00 336+10.00	110.0									35.7					
326+50.00 336+10.00	960.0										51.4	457.4	131.3		154.5
11+50.00 13+04.20	154.2		351.1						35.7		31.8				
332+30.00 RT DRAIN FOR AGGREGATE				3.3											
BASE COURSE															
332+30.00 LT DRAIN FOR AGGREGATE				4.0											
BASE COURSE															
327+10.00 RT ENTRANCE														4.5	18.3
327+10.00 LT ENTRANCE														23.2	94.1
329+78.00 RT ENTRANCE														13.9	56.5
331+52.00 RT ENTRANCE															105.9
332+00.00 LT ENTRANCE														12.4	50.3
334+31.00 LT ENTRANCE														28.4	115.3
100+00.00 101+00.00	100.0														142.3
EMERGENCY ACCESS BYPASS															
SUBTOTAL SECTION 42MFT-T		724.4	1,806.9	1,618.4	191.2	1,444.4	8.0	0.8	145.4	149.3	83.2	457.4	131.3	82.4	737.2
ROUNDED SUBTOTAL SECTION 42MFT-T		725	1,807	1,619	192	1,445	8	1	146	150	84	458	132	83	738
SCHEDULE TOTAL		1,059	2,744	2,825	407	2,399	19	3	259	276	103	620	235	213	1,265

TREE REMOVAL SCHEDULE

LOCATION	TREE REMOVAL (6-15 UNITS DIAMETER) (UNITS)
SECTION 42MFT-BR	
408+54.9 54.40 LT	12
408+61.8 56.80 LT	12
SUBTOTAL SECTION 42MFT-BR	24
SECTION 105-T	
332+63.8 40.9 RT	12
332+55.4 52.2 RT	12
332+73.7 60.5 RT	12
332+67.0 64.9 RT	12
332+52.9 66.9 RT	12
332+48.2 62.8 RT	12
332+46.1 68.1 RT	12
332+38.7 45.1 RT	12
332+28.7 46.2 RT	12
332+26.4 46.5 RT	12
332+19.2 50.5 RT	12
332+16.9 50.9 RT	12
332+13.2 50.2 RT	12
332+06.2 47.4 RT	12
332+02.2 48.1 RT	12
332+00.0 41.4 RT	12
332+28.7 54.4 RT	12
332+25.1 57.5 RT	12
332+22.4 61.3 RT	12
332+14.4 62.0 RT	12
332+03.1 59.6 RT	12
333+84.2 78.8 LT	12
333+83.8 81.3 LT	12
SUBTOTAL SECTION MFT-T	276
SCHEDULE TOTAL	300

PIPE CULVERT SCHEDULE

LOCATION	PIPE CULVERTS CLASS D TYPE 1, 15" (FOOT)	PIPE CULVERTS CLASS D TYPE 2, 15" (FOOT)	STEEL END SECTIONS 15" (EACH)
SECTION 42MFT-BR			
405+36.98 32.91 LT 405+64.90 35.03 LT	28		2
409+19.06 35.21 RT 409+47.89 31.51 RT	30		2
406+65.15 45.40 LT 407+08.07 50.14 LT		44	2
SUBTOTAL SECTION 42MFT-BR	58	44	6
SECTION 42MFT-T			
334+55.5 42.6 LT 334+05.5 61.5 LT	54		2
SUBTOTAL SECTION 42MFT-T	54		2
FROM OTHER SCHEDULES			1
SCHEDULE TOTAL	112	44	9

DELINEATOR SCHEDULE

STATION	OFFSET	DELINEATORS (EACH)
SECTION 42MFT-BR		
408+70.30 38.9 RT		1
SUBTOTAL SECTION 42MFT-BR		1
SECTION 42MFT-T		
331+92.9 63.6 RT		1
332+96.6 53.9 LT		1
SUBTOTAL SECTION 42MFT-T		2
SCHEDULE TOTAL		3

PERMANENT SURVEY MARKERS
TYPE II SCHEDULE

LOCATION	PERMANENT SURVEY MARKERS TYPE II (EACH)
SECTION 42MFT-BR	
SECTION 42MFT-T	1
SCHEDULE TOTAL	2
NOTE: LOCATIONS TO BE DETERMINED BY THE ENGINEER	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAP ROUTE 599 (IL 92)
SECTION 42MFT-BR & 42MFT-T
ROCK ISLAND COUNTY
SCHEDULE OF QUANTITIES
DRAWN BY: HLC

SURVEYED BY: _____ DATE: _____
 ADJUSTED BY: _____ DATE: _____
 CHECKED BY: _____ DATE: _____
 PLAN NO.: _____
 DATE: _____

08/31/2005
 08/31/2005
 08/31/2005
 08/31/2005
 08/31/2005