42000501 PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)

LOCATION		SQ YD	REMARKS
296+25.56 TO 300+00.00	RT	548	RT. TURN LANE
300+00.0 TO 306+00.00	RT	455	RT. TURN LANE
306+00.0 TO 310+37.40	RT	481	RT. TURN LANE
107+67.50 TO 109+82.00		1197	BONUS AVE.
	TOTAL	2681	

42300300 PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH

LOCATION		SQ YD	REMARKS
111+95.00	RT	63	COMMERCIAL ENTRANCE
1015+25.00	RT	100	COMMERCIAL ENTRANCE
	TOTAL	163	

42400200 PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH

LOCATION		SQ FT	REMARKS
107+41.79 TO 109+61.52	RT	1111	
107+63.24 TO 109+62.53	LT	1005	
110+55.74 TO 111+83.05	RT	663	
110+55.99 TO 110+94.84	LT	224	
	TOTAL	3003	

42400800 DETECTABLE WARNINGS

LOCATION		SQ FT	REMARKS
107+45.00	RT	24	
307+76.00	LT	68	
307+90.00	RT	68	
308+93.00	LT	68	
308+95.00	RT	68	
	TOTAL	296	

44000100 PAVEMENT REMOVAL

LOCATION		SQ YD	REMARKS
110+35.00 TO 110+93.00	LT	52.8	
110+35.00 TO 110+74.00	RT	49.7	
	TOTAL	102	

44000500 COMBINATION CURB AND GUTTER REMOVAL

LOCATION		FOOT	REMARKS
107+39.75 TO 107+50.83	RT	9	B-6.18 COMBINATION CONCRETE CURB & GUTTER
107+67.50 TO 109+39.51	LT	167	B-6.12 COMBINATION CONCRETE CURB & GUTTER
107+67.50 TO 109+39.88	RT	172	B-6.12 COMBINATION CONCRETE CURB & GUTTER
	TOTAL	348	

44001430 BITUMINOUS SHOULDER REMOVAL

LOCATION		SQ YD	REMARKS
296+25.56 TO 300+00.00	LT	166	
296+25.56 TO 300+00.00	RT	166	
300+00.0 TO 306+00.00	LT	267	
300+00.0 TO 306+00.00	RT	267	
306+00.0 TO 307+04.67	LT	47	
306+00.0 TO 307+34.95	RT	60	
309+32.32 TO 310+37.41	LT	47	
309+58.04 TO 310+37.41	RT	35	
	TOTAL	1055	

44003100 MEDIAN REMOVAL

LOCATION		SQ FT	REMARKS
307+93.64 TO 308+17.85	LT	272	CONCRETE ISLAND W/CURB
308+56.76 TO 308+81.56	RT	280	CONCRETE ISLAND W/CURB
	TOTAL	552	

44201765 CLASS D PATCHES, TYPE II, 10 INCH

LOCATION		SQ YD	REMARKS
111+98.00 TO 112+02.00	AR	12	18" ERS RCP STORM SEWER
112+98.00 TO 113+02.00	AR	11	18" ERS RCP CULVERT
	TOTAL	23	

48202400 BITUMINOUS SHOULDERS SUPERPAVE 6"

LOCATION		SQ YD	REMARKS
296+25.56 TO 300+00.00	RT	416	10' WIDE SHOULDER
296+25.56 TO 300+00.00	LT	416	10' WIDE SHOULDER
300+00.0 TO 306+00.00	RT	461	10' & VAR. WIDE SHOULDER
300+00.0 TO 306+00.00	LT	667	10' WIDE SHOULDER
306+00.0 TO 307+65.12	RT	73	4' WIDE SHOULDER
306+00.0 TO 307+50.00	LT	131	10' WIDE SHOULDER
309+00.0 TO 310+37.43	RT	87	10' & VAR. WIDE SHOULDER
308+67.22 TO 310+37.43	LT	125	10' & VAR. WIDE SHOULDER
	TOTAL	2376	

50105220 PIPE CULVERT REMOVAL

LOCATION		FOOT	REMARKS
113+00.00	AR	57	12" RCP AR CULVERT
1015+02.0 TO 1015+52.00	RT	50	12" CMP COMMERCIAL ENTRANCE CULVERT
	TOTAL	107	

542A0229 PIPE CULVERTS, CLASS A, TYPE 1 24"

LOCATION		FOOT	REMARKS
303+83.22 TO 303+83.22	RT	7	BUS. RTE. 20 CULVERT EXTENSION
303+83.14 TO 303+83.14	LT	6	BUS. RTE. 20 CULVERT EXTENSION
	TOTAL	13	

542A8203 PIPE CULVERTS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 18"

LOCATION		FOOT	REMARKS
113+00.00 TO 113+00.00	AR	64	AR CULVERT, BONUS AVE.
	TOTAL	64	

542D5470 PIPE CULVERTS, CLASS D, TYPE 1, EQUIVALENT ROUND-SIZE 15"

LOCATION		FOOT	REMARKS
1015+00.0 TO 1015+50.00	RT	50	ENTRANCE CULVERT, MARENGO ROAD
	TOTAL	50	

54214290 END SECTIONS, EQUIVALENT ROUND-SIZE 15"

LOCATION		EACH	REMARKS
1015+00.00	RT	1	ENTRANCE CULVERT ON MARENGO ROAD
1015+50.00	RT	1	ENTRANCE CULVERT ON MARENGO ROAD
	TOTAL	2	

54214503 PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"

LOCATION		EACH	REMARKS
112+75.00	RT	1	STRUCTURE FES-2
112+75.00	LT	1	STRUCTURE FES-1
	TOTAL	2	

PLOT DATE = Thu Nov 18 10:46:23 2005
FILE NAME = P:\MAUPER STUTZ\Projects\Work Order #SUS 28 BR & Bonus Ave\P-92-048-03F(no) From Consultant\7048923SCH.dgn
PLOT SCALE = 1.0000 ' / IN.
REFERENCE = REF