

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
517	L-M-3	BOONE	68	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

54214713 PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 18"

LOCATION		EACH	REMARKS
111+50.00	LT	1	STRUCTURE FES-3
		TOTAL	1

54213657 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"

LOCATION		EACH	REMARKS
113+40.33	RT	1	STRUCTURE FES-4
		TOTAL	1

550A0050 STORM SEWERS, CLASS A, TYPE 2, 12"

LOCATION		FOOT	REMARKS
112+00.00 TO 112+00.00	RT	12	
		TOTAL	12

55035300 STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 23, RISE 14

LOCATION		FOOT	REMARKS
111+50.00 TO 111+50.00	AR	60	
		TOTAL	60

60107600 PIPE UNDERDRAINS 4"

LOCATION		FOOT	REMARKS
299+32.61	RT	9	
112+75.00	RT	4	
		TOTAL	13

60242400 INLETS, SPECIAL

LOCATION		EACH	REMARKS
112+00.00	RT	1	STRUCTURE INL-2, IN DRIVEWAY
113+00.00	RT	1	STRUCTURE INL-1
113+47.83	RT	1	STRUCTURE INL-3
		TOTAL	3

60255500 MANHOLES TO BE ADJUSTED

LOCATION		EACH	REMARKS
109+14.77	RT	1	UTILITY MANHOLE
		TOTAL	1

60265700 VALVE VAULTS TO BE ADJUSTED

LOCATION		EACH	REMARKS
109+03.43	RT	1	WATER VALVE VAULT
		TOTAL	1

60266100 VALVE VAULTS TO BE RECONSTRUCTED

LOCATION		EACH	REMARKS
109+13.61	LT	1	WATER VALVE VAULT
		TOTAL	1

60604400 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18

LOCATION		FOOT	REMARKS
107+39.75 TO 107+50.83	RT	8.8	CURB CUT
107+67.50 TO 109+00.00	LT	132.5	
107+67.50 TO 109+00.00	RT	132.5	
109+00.00 TO 109+80.96	LT	101.2	RADIUS RETURN
109+00.00 TO 109+89.74	RT	129.0	RADIUS RETURN
		TOTAL	504

60605000 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

LOCATION		FOOT	REMARKS
110+42.08 TO 110+93.44	LT	91.7	RADIUS RETURN
110+43.00 TO 111+00.00	RT	94.8	RADIUS RETURN
111+00.00 TO 113+00.00	RT	200.0	
113+00.00 TO 113+86.08	RT	131.1	RADIUS RETURN
		TOTAL	518

63500110 DELINEATORS (SPECIAL)

		EACH	REMARKS
303+83.22	RT	1	CUVLERT EXTENSION
303+83.14	LT	1	CUVLERT EXTENSION
111+50.00	LT	1	STORM SEWER OUTLET
112+75.00	RT	1	AR CULVERT
112+75.00	LT	1	AR CULVERT
1015+00.00	RT	1	ENTRANCE CULVERT
1015+50.00	RT	1	ENTRANCE CULVERT
		TOTAL	7

67000400 ENGINEER'S FIELD OFFICE, TYPE A

	CAL MO	REMARKS
	3	
		TOTAL

67100100 MOBILIZATION

	L SUM	REMARKS
	1	
		TOTAL

70103815 TRAFFIC CONTROL SURVEILLANCE

	CAL DAY	REMARKS
	20	
		TOTAL

70100450 TRAFFIC CONTROL AND PROTECTION, STANDARD 701201

	L SUM	REMARKS
	1	
		TOTAL

70100500 TRAFFIC CONTROL AND PROTECTION, STANDARD 701326

	L SUM	REMARKS
	1	
		TOTAL

PLOT DATE = Thu Nov 18 18:46:08 2005
 FILE NAME = P:\MURPHY STUTZ\Projects\Work\Draw\505 28 BR & Bonus Ave\10-12-04-035.incl From Consultant\204893D1.dgn
 PLOT FILE = 10/18/05 / JL
 REFERENCE = #REF#