

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	13BR-1	WHITESIDE	26	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

# SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	←80% FED-20% STATE→	
			BRIDGE	ROADWAY
			X080-2A	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	1	1
20400805	FURNISHED EXCAVATION, SPECIAL	CU YD	30	30
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	16	16
X2500200	TEMPORARY SEEDING	POUND	40	40
25100630	EROSION CONTROL BLANKET	SQ YD	200	200
28000400	PERIMETER EROSION BARRIER	FOOT	959	959
31101000	SUB GRANULAR MATERIAL B	TON	160	160
44000007	BITUMINOUS SURFACE REMOVAL 2'	SQ YD	144	144
48101200	AGGREGATE SHOULDERS, TYPE B	TON	245	245
48202050	BITUMINOUS SHOULDERS SUPERPAVE 2'	SQ YD	30	30
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1
50300260	BRIDGE DECK GROOVING	SQ YD	620	620
50300300	PROTECTIVE COAT	SQ YD	631	631
50400505	PRECAST PRESTRESSED CONCRETE DECK BEAMS (27" DEPTH)	SQ. FT.	5664	5664
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	7630	7630
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	346	346
51500100	NAME PLATES	EACH	1	1
59000100	EPOXY CRACK SEALING	FOOT	106	106.0
* 63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4
* 63100169	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (FLARED)	EACH	2	2
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2
66300105	CALCIUM CHLORIDE APPLIED	TON	30	30
63301000	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL	FOOT	662	662
63500105	DELINEATORS	EACH	4	4

CODE NUMBER	PAY ITEM	UNIT	←80% FED-20% STATE→	
			BRIDGE	ROADWAY
			X080-2A	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
X7013015	TRAFFIC CONTROL FOR ROAD CLOSURE	L SUM	1	1
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	1856	1856
X4066414	BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE, MIX "C", N50	TON	114	114
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	631	631
X6320100	GUARDRAIL REMOVAL SPECIAL	FOOT	363	363
X0322194	POLYMER MODIFIED PORTLAND CEMENT MORTAR	SQ FT	2.1	2.1
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1

\* SPECIALTY ITEMS

PLOT DATE = Wed Nov 02 13:42:26 2005  
 FILE NAME = c:\p\projects\2005\08\0805\080505.dgn  
 PLOT SCALE = 50.0000 / IN.  
 USER NAME = mgjllj

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. / HORIZ. DATE
DRAWN BY		CHECKED BY