CONTRACT NO. 64A51

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
203	13BR-1	WHITESIDE	26	5
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SCHEDULE OF QUANTITIES

20200600 EXCAVATING AND GRADING EXISTING SHOULDER

UNIT	LOCATION		
0.5	21+ 61.79-	24+ 75	LT & RT
0.5	26+ 47-	28+ 69.58	LT & RT
1	TOTAL		

20400805 FURNISHED EXCAVATION, SPECIAL

CY YD	LOCATION		
15	21+ 61.79-	24+ 75	LT & RT
15	26+ 47-	28+ 69.58	LT & RT
30	TOTAL		

21101615 TOPSOIL FURNISH AND PLACE

CY YD	LOCATION		
10	21+ 61.79-	24+ 75	LT & RT
11	26+ 47-	28+ 69.58	LT & RT
21	TOTAL		

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION		
200	21+ 61.79-	28+ 67	LT & RT
200	TOTAL		

X2500200 TEMPORARY SEEDING

POUND	LOCATION		
20	21+ 61.79-	24+ 75	LT & RT
20	26+ 47-	28+ 69.58	LT & RT
40	TOTAL		

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION		
532	21+ 61.79-	24+ 75	LT & RT
427	26+ 47-	28+ 69.58	LT & RT
959	TOTAL		

28100709 STONE DUMPED RIP RAP, CL A5

TON	LOCATION		
21	24+ 86	LEFT	
21	TOTAL	PLACED ALONG BASE OF STRUCTURE	

31101000 SUB GRANULAR MATERIAL B

TON	LOCATION
160	GOOD NEIGHBOR POLICY
160	TOTAL

X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N50

TON	LOCATION	
7	22+ 55-	24+ 75
7	26+ 47-	26+ 67
100	GOOD NEIGHBOR POLICY	
114	TOTAL	

44000007 BITUMINOUS CONCRETE SURFACE REMOVAL 2"

SQ YD	LOCATION	
72	22+ 55-	24+ 75
72	26+ 47-	26+ 67
72	TOTAL	

48101200 AGGREGATE SHOULDERS, TYPE B

TON	LOCATION	
122	21+ 61.79-	24+ 75
123	26+ 47-	28+ 69.58
245	TOTAL	

48202600 BITUMINOUS SHOULDERS SUPERPAVE 2"

SQ YD	LOCATION	
15.0	24+ 55-	24+ 75
15.0	26+ 47-	26+ 67
30.0		
	TOTAL	

50101500 REMOVAL OF EXISTING SUPERSTRUCTURES

EACH	LOCATION
1	26+ 46.94
1	TOTAL

63100087 TRAFFIC BARRIER TERMINAL, TYPE 6A

EACH	LOCATION	
1	24+ 50.88 -	24+84.78LT
1	24+ 31.82 -	24+65.72RT
1	26+ 56.35 -	26+90.25LT
1	26+ 37.67 -	26+ 71.58RT
4	TOTAL	

63100169 TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (FLARED)

EACH	LOCATION	
1	23+ 13.38 -	23+25.88LT
1	28+ 52.75 -	28+65.25LT
2	TOTAL	

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)

EACH	LOCATION	
1	22+ 6.82 -	22+ 19.32RT
1	28+ 21.58 -	28+34.08RT
2	TOTAL	

63301000 REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL

FOOT	LOCATION	
125	23+25.88 -	24+50.88LT
162	26+90.25 -	28+52.75LT
662	TOTAL	

X6320100 GUARDRAIL REMOVAL, SPECIAL

FOOT	LOCATION	
212.5	22+ 19.32 -	24+ 31.82
150	26+ 71.58 -	28+ 21.58
362.5	TOTAL	

63500105 DELINEATORS

EACH	LOCATION	
1	22+ 6.82	RT
1	23+ 13.38	LT
1	28+ 34.08	RT
1	28+ 65.25	LT
4	TOTAL	

66300105 CALCIUM CHLORIDE APPLIED

TON	LOCATION
30	GOOD NEIGHBOR POLICY
30	TOTAL

78001110 PAINT PAVEMENT MARKING LINE 4"

FOOT	LOCATION		
928	24+ 45.21 -	26+ 76.94	WHITE EDGELINES - 2 COATS
928	24+ 45.21 -	26+ 76.94	DBL YELLOW - 2 COATS
1856	TOTAL		

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

SCHEDULE OF QUANTITIES

PLOT DATE = Wed Nov 02 11:36:59 2005
FILE NAME = c:\pw_pw:\pw1209\PROJ\d80805cvr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = meglilj