

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	127BR-1	HENRY	33	2
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

### SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	X080-2A 80 % FED 20 % STATE	SFTY-3N 80 % FED 20 % STATE
63300456	REMOVAL AND REINSTALLATION OF EXISTING TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	4	
44000007	BITUMINOUS SURFACE REMOVAL 2"	SQ YD	118	118	
44002300	CURB REMOVAL (PARTIAL)	FOOT	17	17	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	16	16	
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1	1	
50102400	CONCRETE REMOVAL	CU YD	9.5	9.5	
50300225	CONCRETE STRUCTURES	CU YD	9.3	9.3	
50300260	BRIDGE DECK GROOVING	SQ YD	622	622	
50300300	PROTECTIVE COAT	SQ YD	666	666	
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	652	652	
50301245	FORMED CONCRETE REPAIR (LESS THAN 5")	SQ FT	966.9	966.9	
50301250	FORMED CONCRETE REPAIR (GREATER THAN 5")	SQ FT	146	146	
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ. FT.	5858	5858	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	9650	9650	
50901005	STEEL BRIDGE RAIL, TYPE SM	FOOT	268	268	
51500100	NAME PLATES	EACH	1	1	
59000100	EPOXY CRACK SEALING	FOOT	29	29	
63302700	REMOVE AND RE-ERECT EXISTING TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63500105	DELINEATORS	EACH	4	4	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. HORIZ. DATE
DRAWN BY		CHECKED BY

PLOT DATE = Thu Nov 03 15:26:49 2005  
 FILE NAME = c:\projects\1208705\080705\vr-dgn  
 USER = pgrout