

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
22	127BR-1	HENRY	33	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	X080-2A 80 % FED 20 % STATE	SFTY-3N 80 % FED 20 % STATE
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION STD 701321	EACH	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION STD. 701201	L SUM	1	1	
70106500	^{TRAFFIC} TEMPORARY BRIDGE SIGNALS	EACH	1	1	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	590	590	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	590	590	
* 78001110	PAINT PAVEMENT MARKING - LINE 4'	FOOT	864	864	
X0323557	BRIDGE JOINT SYSTEM EXPANSION 1'	FOOT	152	152	
X4066414	BITUMINOUS CONCRETE SURFACE COARSE, SUPERPAVE, MIX 'C', N50	TON	20	20	
XX004093	CONCRETE SLOPEWALL REMOVAL	SQ FT	30	30	
XX004094	CONCRETE SLOPEWALL	SQ FT	30	30	
XX005466	FURNISH AND INSTALLING GUARDRAIL END SHOE	EACH	4	4	
* Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	90	90	
Z0002600	BAR SPLICERS	EACH	157	157	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2		2

* SPECIALTY ITEMS

PLOT DATE: Thu Nov 03 14:45:17 2005
 FILE NAME: c:\projects\2005\64B24\64B24.dwg
 PLOT SCALE: 1/8" = 1'-0"
 USER NAME: j.pagnoni

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. _____ HORIZ. _____ DATE _____
DRAWN BY _____		CHECKED BY _____
DATE _____		