CONTRACT NO. 64B24

| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 22 | 127BR-1 | HENRY | 33 | 7 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

# SCHEDULE OF QUANTITIES

mud creek

X4066414 BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N50

| TON | LOCATION | | | | |
|---|---|---|---|---|---|
| 10 | 541+ | 92- | 542+ | 12 | |
| 10 | 543+ | 39- | 543+ | 64 | |
| 20 | TOTAL | | | | |

44000007 BITUMINOUS CONCRETE SURFACE REMOVAL 2"

| SQ YD | LOCATION | | | | |
|---|---|---|---|---|---|
| 65 | 541+ | 92- | 542+ | 12 | |
| 53 | 543+ | 39- | 543+ | 64 | |
| 118 | TOTAL | | | | |

44002300 CURB REMOVAL (PARTIAL)

| FOOT | LOCATION | | | | |
|---|---|---|---|---|---|
| 11 | 542+ | 14- | 542+ | 23 | LT |
| 9 | 541+ | 91- | 542+ | 0 | RT |
| 8 | 543+ | 56- | 543+ | 64 | LT |
| 9 | 543+ | 32- | 543+ | 41 | RT |
| 17 | TOTAL | | | | |

48101200 AGGREGATE SHOULDERS, TYPE B

| TON | LOCATION | | | | |
|---|---|---|---|---|---|
| 4 | 541+ | 94- | 542+ | 25 | LT |
| 4 | 541+ | 68- | 541+ | 99 | RT |
| 4 | 543+ | 58- | 543+ | 89 | LT |
| 4 | 543+ | 32- | 543+ | 63 | RT |
| 16 | TOTAL | | | | |

63302700 REMOVE AND RE-ERECT EXISTING TRAFFIC BARRIER TERMINAL, TYPE 6

| EACH | LOCATION | | | | |
|---|---|---|---|---|---|
| 1 | 541+ | 94- | 542+ | 25 | LT |
| 1 | 541+ | 68- | 541+ | 99 | RT |
| 1 | 543+ | 58- | 543+ | 89 | LT |
| 1 | 543+ | 32- | 543+ | 63 | RT |
| 4 | TOTAL | | | | |

63500105 DELINEATORS

| EACH | LOCATION | |
|---|---|---|
| 1 | 540+ | 17LT |
| 1 | 539+ | 41RT |
| 1 | 545+ | 73LT |
| 1 | 545+ | 40RT |
| 4 | TOTAL | |

78001110 PAINT PAVEMENT MARKING LINE 4"

| FOOT | LOCATION | | | | |
|---|---|---|---|---|---|
| 768 | 541+ | 82 - | 543+ | 74 | WHITE EDGELINES - 2 COATS |
| 96 | 541+ | 82 - | 543+ | 74 | SKIP DASH YELLOW - 2 COATS |
| 864 | TOTAL | | | | |

XX005466 FURNISH AND INSTALLING GUARDRAIL END SHOE

| EACH | LOCATION | | |
|---|---|---|---|
| 1 | 542+ | 25 | LT |
| 1 | 541+ | 99 | RT |
| 1 | 543+ | 58 | LT |
| 1 | 543+ | 32 | RT |
| 4 | TOTAL | | |

| REVISIONS | |
|---|---|
| NAME | DATE |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCALE: VERT. HORIZ.

DATE

DRAWN BY

CHECKED BY

PLOT DATE = Thu Nov 03 14:30:31 2005
FILE NAME = c:\pw_work\d0887805\usr0887805rr.dgn
PLOT SCALE = 50.0000 ' / IN.
USER NAME = raymarl